

CONCRETE AND CONSTRUCTIONAL ENGINEERING

INCLUDING PRESTRESSED CONCRETE

JUNE 1961



VOL. LVI. NO. 6

FIFTY-SIXTH YEAR OF PUBLICATION

PRICE 2s.

ANNUAL SUBSCRIPTION 24s. POST FREE. \$3.90 in Canada and U.S.A.

LEADING CONTENTS

	PAGE
Speed of Construction	205
Book Reviews	208
A Practical Comprehensive Method of Designing Reinforced Concrete Sections—I	
By J. Rygol, B.Sc.(Eng.)	209
A Concrete-lined Tube-railway Tunnel	217
Slabs for Liquid-containing Structures (In accordance with CP. 2007)	219
A Newspaper Office in London	227
Patent Applications for Prestressed Concrete	234

No. 643

ISSUED MONTHLY

Registered for
Canadian Magazine Post

BOOKS ON CONCRETE

For Catalogue of "Concrete Series" books on
concrete and allied subjects, send a postcard to:

CONCRETE PUBLICATIONS LTD., 14 DARTMOUTH ST., LONDON, S.W.1.

INDEX OF ADVERTISERS

	Page		Page
A.B. MOULD & CONSTRUCTION CO. LTD.	viii	LECA (Great Britain) LTD.	—
A.C.E. MACHINERY LTD.	xiv	LEERS OIL & GREASE CO. LTD.	xlii
ARLSON & CO. (ENGINEERS) LTD.	xxviii	LENSCRETA LTD.	xlii
ALLAN, E. P., & CO. LTD.	xlii	LEVINTON (INDUSTRIAL) LTD.	—
ALLIED BUILDING COMMODITIES	xxx	LILLINGTON, GEORGE, & CO. LTD.	xxv
ATLAS STONE CO. LTD.	—	LIND, PETER, & CO. LTD.	v
		LONGDEN, GEORGE, & SON LTD.	—
BARTY, A. & C. LTD.	—		
BERRY'S ENGINEERING CO.	xli	MASER, A. H., LTD.	—
BOULDER EQUIPMENT LTD.	—	MCALL & CO. (SHEFFIELD) LTD.	xli
BOYER, WM., & SONS LTD.	xxvi	MCALLS MACALLOY LTD.	xxviii
BRATHWAITE & CO. ENGINEERS LTD.	—	McKINNEY FOUNDATIONS LTD.	xxxi
B.R.C. ENGINEERING CO. LTD.	lxx	MACHINERY (CONTINENTAL) LTD.	—
BRETT, ROBERT, & SONS LTD.	—	MAGNETE LTD.	xxiii
BRITISH OYSTER CO. LTD.	—	MAY & BUTCHER LTD.	xliv
BRITISH STEEL FILING CO. LTD.	—	MILNARK FLOORS LTD.	xxvii
BUILDING & CONSTRUCTION CO. LTD.	—	MILLARS' MACHINERY CO. LTD.	lv
BYRD, A. A., & CO. LTD.	li	MILLS SCAFFOLD CO. LTD.	x, xi
		MODULAR CONCRETE CO. LTD.	lviii
CABLE COVERS LTD.	lx	MONK, A., & CO. LTD.	—
CALDERONIAN MECHANICAL HANDLING CO. LTD.	—	MULCASTER, WM., & CO. (CONTRACTORS) LTD.	xvii
CAPLIN ENGINEERING CO. LTD.	xxii	MYERS, FRED, LTD.	—
CASTLEHILL SAND & GRAVEL CO. LTD.	—		
CEMENT MARKETING CO. LTD.	ix	OMNIA CONSTRUCTIONS LTD.	—
CEMENT & STEEL LTD.	vi		
CHRISTIAN, ALAN, J. LTD.	xxvii	P.S.C. EQUIPMENT LTD.	xxvi, xxvii
CHEMICAL BUILDING PRODUCTS LTD.	xxix	P.Z. PRESTRESSING CO. LTD.	vii
CHRISTIAN & NIELSEN LTD.	—	PARNLEY & TRICKETT LTD.	xxv
CORNH, GEORGE, SONS & CO. LTD.	—	PITMAN, SIX ISAAC, & SONS LTD.	—
COLCRETE LTD.	xlvii	PORTABLO LTD.	i
CONCRETE FILING LTD.	—	POWELL DUFFY & TUNNICLIFFE INDUSTRIES LTD.	—
CONCRETE PROOFING CO. LTD.	xxii	PRESTRESSING SALES LTD.	—
CONCRETE PUMP CO. LTD.	xv	PREST, B., & SONS LTD.	xx
CONVEYERS & CO. LTD.	xx	PUMPCRAFT HIRE CO. LTD.	xlviii
CONTAIN CONCRETE CO. LTD.	—		
COVIL, WM., & SON LTD.	—	RAHALAN STEEL MOULDES LTD.	xvi
		ROVER CAR CO. LTD.	—
D.A. MODELS LTD.	xi	RUSH & TOMPKINS LTD.	lii
DARDRIDGE, J. & A., LTD.	—	RYLANDS BROTHERS LTD.	—
DAVIDSON'S PAPER SALES LTD.	—		
DE JONG	iv	SEALOCRETE PRODUCTS LTD.	xxi
DICKENS, STUART B., LTD.	xli	SHARP JONES & CO. LTD.	—
DURMAN LONG & CO. LTD.	xvii	SIMPLEX CONCRETE PILES LTD.	—
DOUGLAS, ROBERT M. (CONTRACTORS) LTD.	—	SOMERSET WIRE CO. LTD.	liii
DURATUBE & WIRE LTD.	—	STELINS LTD.	—
		STENT PRECAST CONCRETE LTD.	—
ENGINEERING DESIGN & CONSTRUCTION LTD.	xxiv	STIC B PAINT SALES LTD.	—
EXPANDITE LTD.	—	STONE COURT BALLAST CO. LTD.	—
		STOKER, WM. T., & CO. LTD.	xxviii
FARR, A. H., LTD.	—	STRENGTH DEVELOPMENTS LTD.	—
FLEXIBLE DRIVE & TOOL CO. LTD.	xvii	STUART'S GRANULITIC CO. LTD.	—
FORD MOTOR CO. LTD.	xvii	SUSSEX & DORSET BRICK CO. LTD.	—
FRANKFILL LTD.	xv		
		TARMAC LTD.	—
G.K.N. REINFORCEMENTS LTD.	liv	TECHNICAL PAINT SERVICES	xviii
GILSON, M. J. (CONTRACTORS) LTD.	—	TENTON BAR CO. LTD.	lxix
GOODS ENGINEERING LTD.	—	THAMES PLYWOOD MANUFACTURERS LTD.	—
GUNITE CONSTRUCTION CO. LTD.	xxviii	TILEMAN & CO. LTD.	—
		T.P. POLYPLASTIC CONVERTERS LTD.	—
HALL & CO. LTD.	—	TRENT GRAVELS LTD.	lxviii
HILTON GRAVEL LTD.	—	TRITON ENGINEERING CO. (SALES) LTD.	xi
HOLMES & CO. LTD.	—	TRUCK-MIX (MIDLANDS) LTD.	—
HOLST & CO. LTD.	—	TUNNEL PORTLAND CEMENT CO. LTD.	—
HUNTLEY & SPARKS LTD.	xxx		
		UNISTRUT DIVISION OF SANKEY-SHELDON LTD.	—
IDEAL CEMENTS (READING) LTD.	—		
IMPERIAL CHEMICAL INDUSTRIES LTD.	lvii	VOLKMAN, O. A.	—
JOHNSON, RICHARD, & NEPHEW LTD.	xxvii	WALKER WEIGHT & CO. LTD.	—
JONES, T. C., & CO. LTD.	—	WELSH TRADING CO. LTD.	xxiii
		WELLSMAN BROS. LTD.	—
KERNER-GREENWOOD & CO. LTD.	—	WESTWOOD, JOSEPH, & CO. LTD.	—
KING, J. A., & CO. LTD.	xxv	WHITECROSS WIRE CO. LTD.	xix
		WHITHEAD IRON & STEEL CO. LTD.	—
LAFARGE ALUMINOUS CEMENT CO. LTD.	lvi	WHITLEY MORAN & CO. LTD.	—
LAWLER AYERS & CO. LTD.	—	WINGET LTD.	—
LAW & SON (STAINES) LTD.	xxx	WOLF ELECTRIC TOOLS LTD.	—
		YORKSHIRE HENNESIQUE CONTRACTING CO. LTD.	—

TRITON

REGD TRADE MARK

**VIBRATING SYSTEMS
FOR PRECAST CONCRETE
WORK ON THE SITE**

Triton vibrating systems provide the contractor with a completely planned vibrating unit for the production of precast concrete on the site. Our technical advice service will be pleased to suggest a comprehensive plan, using both fixed tables and mobile 'Vibra-Lifta' tables, which will show the economy and efficiency to be obtained from using a Triton vibrating system on the site.

FIXED

Two Triton tables, each 4' x 4' vibrating a 15' purlin. These tables can be mounted on concrete blocks of any required height.



MOBILE

Two Triton mobile 'Vibra-Lifta' tables, vibrating a 25' beam. These 'Vibra-Lifta' tables can be moved at will over the site.



**THE
TRITON**

ENGINEERING CO (SALES) LTD

(in association with Triton Engineering Co. Ltd)

KINGSMOUTH INDUSTRIAL ESTATE, WOTTON ROAD, ASHFORD, KENT

Telephone: Ashford 2861-2-3 Telegrams: Triton Ashford Kent

INDEX OF ADVERTISERS

	Page		Page
A.B. MOULD & CONSTRUCTION CO. LTD.	xviii	LECA (GREAT BRITAIN) LTD.	—
A.C.E. MACHINERY LTD.	xv	LEESA OIL & GRAIN CO. LTD.	xiii
ASHLON & CO. (ENGINEERS) LTD.	xxviii	LEWIS & CO. LTD.	xiii
ALLAN, R. P., & CO. LTD.	xix	LEVINTON (INDUSTRIAL) LTD.	—
ALLIED BUILDING COMMODITIES	xxx	LELLINGTON, GROOMER, & CO. LTD.	xixv
ATLAS STONE CO. LTD.	—	LIND, PETER, & CO. LTD.	v
		LENGERT, GEORGE, & SON LTD.	—
BARVE, A. & C. LTD.	—		
BERRY'S ENGINEERING CO.	xii	MAGNET, A. H., LTD.	—
BOULDER EQUIPMENT LTD.	—	MCCALL & CO. (SHEFFIELD) LTD.	xii
BOYER, W.S., & SONS LTD.	xixvi	MCCALLA MACALLOY LTD.	xxviii
BRAITHWAITE & CO., ENGINEERS LTD.	—	MCCLINNEY FOUNDATIONS LTD.	xxxi
B.R.C. ENGINEERING CO. LTD.	lxx	MACHINERY (CONTINENTAL) LTD.	—
BRETT, ROBERT, & SONS LTD.	—	MAGNETE LTD.	xxiii
BRITISH OXYGEN CO. LTD.	iii	MAY & BUTCHER LTD.	xix
BRITISH STEEL PILING CO. LTD.	—	MILBURN FLOORS LTD.	xxvii
BUILDING & CONSTRUCTION CO. LTD.	—	MILLAR'S MACHINERY CO. LTD.	iv
BYRD, A. A., & CO. LTD.	ii	MILLS SCAFFOLD CO. LTD.	x, xi
		MODULAR CONCRETE CO. LTD.	lxviii
CABLE COVERED LTD.	ix	MONK, A., & CO. LTD.	—
CALDERIAN MECHANICAL HANDLING CO. LTD.	—	MULCASTER, WM., & CO. (CONTRACTORS) LTD.	xvii
CAPLIN ENGINEERING CO. LTD.	xvii	MYERS, FRED, LTD.	—
CANTERBURY SAND & GRAVEL CO. LTD.	—		
CEMENT MARKETING CO. LTD.	ix	OMNIA CONSTRUCTIONS LTD.	—
CEMENT & STEEL LTD.	vi		
CHETNAM, ALAN, J., LTD.	xixvi	P.B.C. EQUIPMENT LTD.	xixv, xixvi
CHEMICAL BUILDING PRODUCTS LTD.	xxix	P.Z. FRUITREDDING CO. LTD.	vii
CHRISTIAN & MILLER LTD.	—	PAWLEY & TRICENT LTD.	xix
CHURCH, GEORGE, & SONS & CO. LTD.	—	PITMAN, SIR ISAAC, & SONS LTD.	—
CILCRETE LTD.	xviii	PORTABLO LTD.	i
CONCRETE PILING LTD.	—	POWELL DUFFY'S TIMBER INDUSTRIES LTD.	—
CONCRETE PROTECTING CO. LTD.	xvii	PRESTRESSING SALES LTD.	—
CONCRETE PUMP CO. LTD.	xiv	PRINCE, B., & SONS LTD.	xi
CONCRETE & CO. LTD.	xi	PURCHETT HIRE CO. LTD.	xviii
CONTAIN CONCRETE CO. LTD.	—		
COVILL, W.S., & SON LTD.	—	RAHALAN STEEL MOUNDS LTD.	xvii
		ROVER CAR CO. LTD.	—
D.A. MODELS LTD.	xi	RUSS & TOMPAIS LTD.	ix
DANDRIDGE, J. & A., LTD.	—	RYLANDS BROTHERS LTD.	—
DAVIDSON PAPER SALES LTD.	—		
DE JONG	iv	SHALCRETE PRODUCTS LTD.	xii
DICKENS, STUART B., LTD.	xii	SHARP JONES & CO. LTD.	—
DORMAN LONG & CO. LTD.	xvii	SIMPLEX CONCRETE PILES LTD.	—
DOUGLAS, ROBERT M. (CONTRACTORS) LTD.	—	SOMERSET WIRE CO. LTD.	lv
DURATURE & WISE LTD.	—	STELMO LTD.	liii
		STENT PRECAST CONCRETE LTD.	—
ENGINEERING DESIGN & CONSTRUCTION LTD.	xxixv	STIC & PAINT SALES LTD.	—
EXPANITE LTD.	—	STONE COURT BALLAST CO. LTD.	—
		STORER, WM. T., & CO. LTD.	xxviii
FARR, A. E., LTD.	—	STRENGTH DEVELOPMENTS LTD.	xxix
FLEXIBLE DRIVE & TOOL CO. LTD.	xixv	STUART'S GRANULITIC CO. LTD.	—
FORD MOTOR CO. LTD.	xvii	SUSSEX & DORSET HIRE CO. LTD.	—
FRANKFILL LTD.	xv		
		TARMAC LTD.	—
G.K.N. REINFORCEMENTS LTD.	liv	TECHNICAL PAINT SERVICES	xviii
GILSON, M. J. (CONTRACTORS) LTD.	—	TRITON BAR CO. LTD.	lxix
GOODS ENGINEERING LTD.	—	THAMES FLYWOOD MANUFACTURERS LTD.	—
GUNITE CONSTRUCTION CO. LTD.	xxviii	TILEMAN & CO. LTD.	—
		T.P. POLYPLASTIC CONVERTERS LTD.	—
HALL & CO. LTD.	—	TREST GRAVELS LTD.	lxviii
HILTON GRAVEL LTD.	—	TRITON ENGINEERING CO. (SALON) LTD.	xi
HOLMERS PILES LTD.	—	TRUCE-MIX (MIDLANDS) LTD.	—
HOLST & CO. LTD.	—	TUNER PORTLAND CEMENT CO. LTD.	—
HUNTLEY & SPARES LTD.	xxx		
		UNIDENT DIVISION OF SAREY-SERLON LTD.	—
IDEAL CEMENTS (READING) LTD.	—		
INFERNAL CHEMICAL INDUSTRIES LTD.	lvii	VOLKMAN, O. A.	—
JORDON, RICHARD, & NEWMAN LTD.	xxvii	WALKER WHERRY & CO. LTD.	—
JONES, T. C., & CO. LTD.	—	WELLS TRADING CO. LTD.	xliii
		WILLIAMS BROS. LTD.	—
KERR-GREENWOOD & CO. LTD.	—	WHITWOOD, JOSEPH, & CO. LTD.	—
KING, J. A., & CO. LTD.	xixv	WHITCOMB WIRE CO. LTD.	xix
		WHITENAD IRON & STEEL CO. LTD.	—
LAFARGE ALUMINOUS CEMENT CO. LTD.	lv	WHITLEY MORAN & CO. LTD.	—
LAWLER AYLES & CO. LTD.	—	WINGET LTD.	—
LAW & SON (STAINES) LTD.	xxx	WOLF ELECTRIC TOOLS LTD.	—
		YORKSHIRE HENNINGER CONTRACTING CO. LTD.	—

TRITON

REGD TRADE MARK

**VIBRATING SYSTEMS
FOR PRECAST CONCRETE
WORK ON THE SITE**

Triton vibrating systems provide the contractor with a completely planned vibrating unit for the production of precast concrete on the site. Our technical advice service will be pleased to suggest a comprehensive plan, using both fixed tables and mobile 'Vibra-Lifta' tables, which will show the economy and efficiency to be obtained from using a Triton vibrating system on the site.

FIXED

Two Triton tables, each 4' x 4' vibrating a 15' purlin. These tables can be mounted on concrete blocks of any required height.



MOBILE

Two Triton mobile 'Vibra-Lifta' tables, vibrating a 25' beam. These 'Vibra-Lifta' tables can be moved at will over the site.



**THE
TRITON**



ENGINEERING CO (SALES) LTD

(In association with Triton Engineering Co. Ltd)

KINGSDOWN INDUSTRIAL ESTATE, WOTTON ROAD, AMFORD, KENT

Telephone: Ashford 2651-53 Telex: Triton Ashford Kent

TRUCK MIXERS



Available in several capacities, either with
petrol or Diesel engine or power take-off.

Quick and intensive mixing.

Quick charging and discharging.

DE JONG

HAZERSWOUDE HOLLAND

P.O. Box 88 LEIDEN

Over 40 years' experience in the construction
of contractors machinery.

DRILLED FOUNDATIONS



Architects
Consulting Engineers
Main Contractors

Sir John Burnet, Tait and Partners
Ove Arup and Partners
Frostup and Collis Limited

A modern office block which is being erected on our drilled foundations at Vauxhall Bridge Rd. London for Chesterfield Properties Limited

We have modern mobile plants which can drill foundations of various diameters up to depths of 100 feet or more. Tel: Abbey 7361 or send your enquiries to

PETER LIND

Peter Lind and Company Limited Romney House Tufton Street London SW1



POWER BAR CUTTERS

The BRRL.50A model, illustrated above, will meet all requirements for high speed, economy, and simplicity of operation. This high-speed shearing machine will cut mild steel rods up to 2 in. diameter. It is of robust construction yet portable in view of its compact arrangement, and is powered by electric motor and self-tensioning Vee-belt drive. The moving blade is in continuous action and makes 28 cuts per minute; 2-in. diameter bars require one cut only. The static blade is housed in a specially designed seating which spreads the shearing thrust over a wide area, thus reducing wear and considerably lengthening the life of the machine. Diesel-driven machines also available. Let us send you full details.

CEMENT & STEEL, LTD., SECOND AVENUE, CHATHAM, KENT.

Telephone: Chatham 45580. Telegrams: Cembelgi, Chatham.



the modern method of



PRESTRESSED CONCRETE DESIGN AND CONSTRUCTION

**FOR
INSITU AND
PRECAST
STRUCTURES
OF ALL TYPES**

This system is described and illustrated in our Catalogue, together with some of the many important contracts on which it has been used. Engineers and Contractors interested in the latest developments should send for a copy.


THE PZ PRESTRESSING CO. LTD.

BURCOTT LODGE, BURCOTT, WING, LEIGHTON BUZZARD.

TELEPHONE: WING 286

AB MOULDS

**CAN BE RELIED UPON TO
GIVE CONSISTENT SERVICE
OVER MANY YEARS**



The above illustration of a standard garden edging mould shows the tough construction of our moulds, which reduces expenditure on maintenance and constant replacement of moulds of less robust design.

A. B. MOULD & CONSTRUCTION CO., LTD.

**VULCAN WORKS, VULCAN WAY
NEW ADDINGTON, SURREY**

Telephone : Lodge Hill 2347

Telegrams : Abmould, Croydon



Throughout the U.K. the Blue Circle Group of Companies has 29 cement works and 30 manufacturing plants at which are produced Blue Circle, Pelican and Dragon brands of Portland Cement, Ferrocrete, '417' Cement, Aquacrete, Sulfacrete, Hydracrete, Walcrete, Snowcrete, Colorcrete, Hydralime, Whiting, Super Snowcem, etc. It has 16 district offices and a network of distribution centres. The road transport owned by the Group includes over 1,200 vehicles for delivery in bag or in bulk, and it


operates one of the largest fleets of tugs and lighters on the Thames and Medway.

The Blue Circle Group is the largest cement manufacturing organisation in the world. You are invited to make use of its many services and profit from its great resources.

Blue Circle Products are exported to countries all over the world and the Group also has interests in twelve works overseas, nine of which are in the Commonwealth.




The Cement Marketing Company Limited,
Portland House, Tothill Street, London, S.W.1. Telephone TATe Gallery 3456
G. & T. Earle Limited, Hull. Telephone Hull 26121
The South Wales Portland Cement & Lime Co. Ltd., Penarth, Glam.
Telephone Penarth 57301-4




V800's spanning approximately 52 feet, with double under trussing.

MILLS



This photograph illustrates the fine adjustment of spans which can be obtained with the V800.



V800's with double under trussing, spanning about 56 feet.



4ft 1 1/4 in. - 5ft 9 in.



END SECTION

4ft 11 in.

INTERMEDIATE
SECTION

7ft 4 1/2 in.

INTERMEDIATE
SECTION

4ft 1 1/4 in. - 5ft 9 in.



END SECTION

V800

ADJUSTABLE TRUSS

for heavy duty support to formwork

The Mills V800 Adjustable Truss is the ideal way of providing heavy duty support to formwork over long clear spans. It is assembled, basically, from end sections, adjustable from 4' 1 1/4" to 5' 9" and intermediate sections in lengths of 4' 11" and 7' 4 1/2". The carrying capacity of the beam can be considerably increased by employing under-tensioning members as a truss. The swivel connections make it possible, by the adjustment of turn-buckles in the lower chord, to use the beam either straight, cranked or arched. Mills V800 Adjustable Truss is available for sale or hire.

PLANNING SERVICE

A planning service is available for users of the V800 Adjustable Truss, providing drawings for specific requirements and erection supervision on major contracts.

MILLS SCAFFOLD CO. LTD.

Trussley Works, Hammersmith Grove,
London W.6. (Riverside 3011)



Depots: BIRMINGHAM · BOURNEMOUTH · BRADFORD
BRIGHTON · BRISTOL · CANTERBURY · CARDIFF · COVENTRY
CROYDON · DUNDEE · EDINBURGH · GLASGOW · HASTINGS
HULL · ILFORD · LEICESTER · LIVERPOOL · LONDON
MANCHESTER · MIDDLESBROUGH · NEWCASTLE · NOTTINGHAM
OXFORD · PRESTON · PLYMOUTH · PORTSMOUTH
READING · ROTHERHAM · SOUTHAMPTON · SWANSEA

FABRIC REINFORCEMENT by McCALLS

FABRIC • BARS • TENTOR • BENDING • MACALLOY • DESIGN

McCALL & CO (SHEFFIELD) LTD.

McCALLS MACALLOY LIMITED

TEMPLEBOROUGH • SHEFFIELD • ENGLAND • P.O. BOX 41

Telephone: ROTHERHAM 2078 (P.B. Ext 9 lines)

LONDON: SLOANE 0428

BIRMINGHAM: ACOCKS GREEN 0229

PORTSMOUTH: COSHAM 78702

MANCHESTER: BLACKFRIARS 1018

35 MILLION YARDS OF CONCRETE PROVE

that **ritecure**
METHOD OF CURING

is completely reliable

. . . That's the measure of concrete cured with the RITECURE method in the British Isles *alone*. Or to put it another way—it has been used on over 90% of the major concrete road and runway contracts in this country. In fact, you will find testimony to RITECURE all over the world—even as far away as the Khyber Pass.


- One application of RITECURE saves labour
- Ensures correct curing without further worry



Used on the concrete section of the M.1.
Everybody knows about RITECURE, but if you want to know more, write for the free literature:

STUART B. DICKENS LIMITED

Manor Way, Boreham Wood, Hertfordshire. Telephone: ELstree 2217



An Electrically Driven PC3 Concrete Pump with remixer. Capacities from 20 to 24 cu. yds. per hour. Ranges actually obtained 135 ft. vertical or 1,500 ft. horizontal. Also smaller model PC4—8-10 cu. yds. per hour.

EFFICIENT RECONDITIONING SERVICE

CONCRETE BY PUMP AND PIPELINE

- The most efficient method of placing concrete.
- Life of Pump practically indefinite: all essential surfaces in contact with concrete are renewable.
- Pumpable concrete must of necessity be good concrete.
- Pump and Mixing Plant can be located at the most convenient position within the pumping range.
- The continuous output of the Pump at a constant speed governs the working of the whole concreting gang.

THE REGISTERED TRADE MARK OF

PUMPCRET

THE CONCRETE PUMP COMPANY LIMITED

THE CONCRETE PUMP COMPANY LTD

4 STAFFORD TERRACE, LONDON, W.8

Telephone: Western 3546

Telegrams: Pumpcret, Kens, London


FRANKI facts

BARRETT'S CAR SHOWROOM • CANTERBURY



PROBLEM The site was in a new development area, immediately adjacent to a building which had not been piled, and the basement excavation would have necessitated underpinning the existing building. Because of the nature of the strata,

STRATA



all foundations in the area have to be taken down to ballast, and water in the ballast has caused difficulty with mass concrete foundations leading to delays with the structures and additional expense.

SOLUTION Franki bored piles of 16" diameter reinforced with four $\frac{1}{2}$ " dia. rods with $\frac{1}{2}$ " helical binding at 6" pitch were installed from general ground level, effecting maximum speed of progress with maximum economy. The water was dealt with during the normal course of operations, and general excavation for the basement area was carried out after piling was complete. Some piles were installed with their centres 1' 6" from the outside face of the party wall.

Contract No: 3529 • Client: Barretts Limited

Location: Rose Lane, Canterbury • Architect: John C. Clague, L.R.I.B.A.

Engineers: Concrete (Southern) Limited • General Contractors: Richard Costain Limited

Type of Structure: Car Showroom • Number and Type of Piles: 53 Franki Bored

Working Load: 35 tons • Average Length: 13' 0" (below basement level)

FRANKI

At your Service throughout the World

FRANKIPILE LIMITED • 39 VICTORIA STREET • LONDON S.W.1 • TEL: ABBEY 6006/9


FOR CONCRETE PRODUCTS



RANALAH

STEEL
MOULDS

CUT CAPITAL COSTS
BETTER CASTS & MORE
CASTS PER MOULD



GARAGES, COAL BUNKERS, MILLS,
COPING STONES, AGRICULTURAL AND
INDUSTRIAL BUILDINGS, FENCING POSTS,
KERBS, GARDEN EDGING, ETC.



RANALAH STEEL MOULDS LTD

LOWER BEVEDEAN

BRIGHTON

SUSSEX TEL: 62216-78



POWER for industry

Our range of industrial engines are a practical proposition for many types of industrial equipment... compressors, cranes, pumps, contracting equipment, earth borers, generators, railcars, welding plant, works trucks, tractors and conversions. Simple design, modern flow-line production methods and common interchangeable parts contribute to the low cost of these high efficiency engines. And remember, every engine is fully backed by a World-wide Parts and Service Organi-

sation. Take your choice from a wide power range... Diesel 20 to 86 b.h.p. and Petrol 11 to 87 b.h.p. (12-hr. rating).

DIESEL ECONOMY—have you considered the replacement of existing power units in your equipment and trucks with the famous 4D Diesel engine? You'll have the unique advantages of economy, long-life and low running costs... plus the best service in the World!

Wherever you are, whatever your problem,



**MOTOR COMPANY LIMITED
ENGLAND**

are at your service

For further details of our

INDUSTRIAL ENGINES

and the equipment they power,
send the coupon to your nearest Ford Dealer
or direct to

FORD MOTOR COMPANY LIMITED · PARTS DIVISION (G51) · AVELEY DEPOT · SOUTH OCKENDON · ROMFORD · ESSEX · ENGLAND

Please send me technical brochures of your
*PETROL/DIESEL Industrial Engines. The
maximum B.H.P. required is.....at.....
R.P.M. Also, please send details of the follow-
ing equipment powered by your engines.

Name.....


Address.....

Nature of Business.....

Telephone No.

* Delete where not applicable

G51-23-6



Tel.: UXBRIDGE
33399

T.P.S.

SHUTTERING and MOULD PAINTS

will make your shuttering and moulds last longer,
often save the labour costs of repeated mould oil
application, and are also the cheapest alkali
primers for general use under paint work


*Reduced costs and clean concrete surfaces are always obtained from shutters and
moulds treated with these paints. Wood grain is filled and sealed against water and
alkali. Douglas Fir staining eliminated*

Ask for the type for YOUR purpose
SPECIAL TYPES FOR PLYWOOD,
STEEL OR CONCRETE SURFACES
TO SUIT ALL REQUIREMENTS

PROMPT DELIVERY FROM STOCK!

TECHNICAL PAINT SERVICES, DEPT. C.G.E.

THE PAINT CENTRE — UXBRIDGE — MIDDLESEX



MODERN *PRESTRESSING* METHODS

**DEMAND THE FINEST
HIGH TENSILE WIRES AND STRAND**

Strand type

Plain Crimped

Indented type B

Indented type C

Whitecross wire and strand is currently being used in many prestressed projects both at home and abroad. Stress-relieved high tensile wire by Whitecross satisfies the most exacting requirements of architects, civil engineering consultants and contractors throughout the world. Among other projects it was used in the construction of the city of Birmingham Ring Road, and the Embassy of the United States of America in London.

The Whitecross company has played a leading part in the development of large diameter strands for use with post-tensioning systems employing wedge grip anchorage.

Whitecross technical experts are always willing to give advice on any problems you may have on prestressing matters.

WHITECROSS

THE WHITECROSS COMPANY LIMITED

WARRINGTON · ENGLAND

TELEPHONE: WARRINGTON 3881





Bp

BOLTS & NUTS

TIE-RODS

ETC.

FOR THE CONTRACTOR



Manufactured by

B. PRIEST & SONS LTD · OLD HILL · STAFFS · ENG.

Telephone: Cradley Heath 66501 (8 lines)



42" diameter to 27" diameter straight back mould for manhole tapers.

Moulds and formwork

for the concrete industry

A service to the industry ranging from the small equipment illustrated to complete spinning plants, backed by years of technical experience.

We are now operating from our extensive new premises at the address below.

Further details and quotations sent on request

Coneybeare

THE ORIGINAL PIPE MOULDS

Coneybeare & Co. Ltd., Torrington Road, Ashford, Kent. Tel: Ashford 1545/6

**FOR THE LONG HAUL
RELY
ON**

PLAZCRETE

THE MODERN AID FOR A WELL-DESIGNED CEMENT MIX

PLAZCRETE RETARDS THE SET

Permits longer haulage time
Avoids day joint problems

PLAZCRETE IMPROVES WORKABILITY AND PLASTICITY

Makes pumping easier
Saves time placing and vibrating
Improves consolidation, particularly around reinforcement

PLAZCRETE PERMITS A REDUCED WATER/ CEMENT RATIO

Reduces shrinkage
Eliminates laitance, bleeding and segregation

PLAZCRETE IN THE MIX REDUCES THE COST WITHOUT ANY LOSS OF STRENGTH

For further information write to Dept. PC.:

SEALOCRETE PRODUCTS LTD.,
ATLANTIC WORKS, HYTHE ROAD,
LONDON, N.W.10.

Telephone: Ladbroke 0015, P.B.E.
Telegrams: Sealocrete, Wesphone, London.

N.B. When retarding of the set is not required Plazcrete (Non-retarding) can be supplied.




CONCRETE PROOFING Co. LTD.

GUNITE SPECIALISTS

Expert advice and schemes submitted for gunite work of every kind. Complete information on the various uses of gunite will be gladly sent on request

116 Richmond Road, Kingston-upon-Thames, Surrey- ^{Telephone: KINGSTON 7883 and 9251}
And 10 Royal Crescent, Glasgow, C.3. ^{Telephone: GLASGOW DOUGLAS 8671}



For compacting mortar cubes
for compression tests to

B.S. 12/1958, 146, 1370, 915

Automatic Time Control

"CAPCO"

H.F. VIBRATOR

"CAPCO" CONCRETE TESTING APPARATUS also includes:
Cube Moulds; Slump Cones; Tensile, Vicat and Cylindrical
Moulds; Compacting Factor Apparatus—Standard and Auto-
matic; Sieve Vibrators and Sieves; etc.

CAPLIN ENGINEERING CO. LTD
(ESTABLISHED 1918)


POLLEN HOUSE, 10/12 CORK STREET, LONDON, W.1

Phone: REGENT 0716. Grams: CAPLINKO, LONDON. Telex: 23255. Cables: CAPLINKO, LONDON. Works: IPSWICH.

A Finer Finish
at Lower Cost



MASONITE SHUTTERING

forms Better Concrete



Large sheets of
SWEDISH MADE
MASONITE
tempered presdwood

SIZES $\frac{1}{4}$ " — $\frac{3}{8}$ " — $\frac{1}{2}$ " — $\frac{3}{4}$ "



For continuous and repetitive use, where reliability and speed are essential, Masonite $\frac{1}{4}$ " and $\frac{3}{8}$ " Tempered Presdwood is the ideal form liner made especially for concrete work available in sheets 4' x 9' and 8'.

For curved shuttering down to a 9" radius, specify Masonite $\frac{1}{4}$ " Tempered Presdwood, the 'companion' shutter board that gives a smooth form finished concrete and lightens shuttering assembly work.



MASONITE LIMITED

BEVIS MARKS HOUSE, BEVIS MARKS,
LONDON, E.C.3

Tel: AVENUE 2846 Grams: Etinosam, Fen, London

May we
PRECAST
 your
STRUCTURAL
COLUMNS

and
 SAVE TIME SAVE MONEY

J. A. KING & Co., LTD

181 Queen Victoria St., LONDON, E.C.4

Telephone: CENTral 5866 (5 lines)

Telegrams: Kinovique Cent London



Model VP 350-A (Swivel Base or Barrow Mounting)

Prompt Delivery. Highly Competitive Prices. Genuine Service. Re-Sale Terms Available.

* We operate a 48-hour Shaft Repair Service for all makes. Write to-day for 8-page fully descriptive Catalogue. Agents throughout the world.

30 years' experience in the design and manufacture of flex-shaft tools.

THE FLEXIBLE DRIVE & TOOL CO., LTD.

EDENBRIDGE, KENT. Telephone: 3385-6

LONDON OFFICE: 17 QUEENSBERRY WAY, S.W.7. Telephone: KENington 3583

For Greater Strength, Firmer Bonding
 and Better Surfacing of Concrete—

"BAXTUL"

Repd. Trade Mark


British Made

Extra-High Frequency

INTERNAL CONCRETE VIBRATORS

- The model illustrated here operates at 9,000 to 15,000 Vibrations per minute from low flexible shaft speeds of 4,500 to 7,500 R.P.M.
 - Petrol or Electric Drive.
 - Robustly built throughout and backed by genuine service.
 - Fitted centrifugal clutch, long-life flexible drive and Vibrator.
- This unique machine, with quick-change additional tools, can also be used for: SURFACING, WET-RUBBING CONCRETE, GRINDING, DISC SANDING, AND DRILLING (up to 1½" in Concrete, 1" in Steel, and 2" in Wood).

REINFORCEMENT by Pashley & Trickett

*philips*

We specialise in providing accurately bent steel reinforcement for any size of concrete constructional work. Supply us with your bending and delivering schedules and we will supply to your site clearly identified steel reinforcement as and when it is required. All enquiries are dealt with promptly.




PASHLEY & TRICKETT LTD
STOKE STREET, SHEFFIELD 9
TELEPHONE: 41136-7

FREYSSINET PRESTRESSING




**FREYSSINET MULTISTRAND 12 1/4"
TENSIONING JACK**



FREYSSINET 12/276 ANCHORAGE

FREYSSINET PRESTRESSING


The Freyssinet system of prestressing provides a means of stressing and anchoring 12-wire cables simultaneously. Anchorages are available for the following sizes of cables: 12/200 (5 mm.), 12/276 (7 mm.), and 12/8 mm.



FREYSSINET MULTISTRAND 12 1/4" ANCHORAGE

FREYSSINET MULTISTRAND SYSTEM

The introduction of the MultiStrand system was a natural step in the development of Freyssinet prestressing techniques. The system is based upon the use of a cable of 12 No. 7-wire strands each of 1/4" diameter. The whole 12 1/4" cable is stressed in a single operation and provides an initial design force of approximately 140 tons.



FREYSSISTRAND 1 1/4" ANCHORAGE

FREYSSISTRAND SYSTEM

The Freyssistrand system was developed to facilitate the use of large diameter multi-layer strand. The system is designed for use with the following sizes of strand: 1 1/4" and 1 3/4" diameter.



The range of prestressing service which the Freyssinet and P.S.C. Organisation can offer is as broad as the very problems to be resolved. These services are available to all concerned with the design, manufacture and construction of prestressed concrete structures.

PIONEERS OF PRESTRESSED

PSC PRESTRESSING



**P.S.C. MONOWIRE
POST-TENSIONING JACK**

P.S.C. MONOWIRE SYSTEM

This system of prestressing provides a greater variation of prestressing force than heavier systems and was produced for this particular reason. It is based on the tensioning of wires individually.



P.S.C. MONOWIRE 12/276 ANCHORAGE

P.S.C. MONOSTRAND SYSTEM


This system has been developed to provide a variable range of prestressing forces by tensioning strands individually. Anchorages are available for the following sizes of strand: $\frac{3}{16}$ ", $\frac{1}{4}$ ", $\frac{5}{16}$ " and $\frac{3}{8}$ ".



P.S.C. MONOSTRAND $\frac{1}{2}$ " ANCHORAGE

P.S.C. PRETENSIONING SYSTEMS

P.S.C. pretensioning jacks are available for use with all sizes of wire up to 0-276 (7 mm.) or strand up to $\frac{1}{2}$ " dia. A large range of anchorage sizes is available for use with both strand and wire.



P.S.C. SPRING-LOADED MULTI-USE ANCHORAGE

PSC



EQUIPMENT LTD

HEAD OFFICE AND WORKS: ARUNDEL ROAD, INDUSTRIAL TRADING ESTATE, UXBRIDGE, MIDD
Telephone: Uxbridge 35241

CONCRETE IN GREAT BRITAIN

STORER'S



Sawing, Planing and Moulding Mills and Storage Yards at Barking

for

SOFTWOOD


Wm. T. STORER & CO. LTD.

Timber Importers and Merchants

ESTABLISHED 1913

Telephone: RIPPleway 0301 (10 lines)

RIVER ROAD - BARKING - ESSEX



OUTSTANDING BUILDING . . .

Outstanding products . . .

**CHEMICAL
BUILDING
PRODUCTS
LIMITED**
Warple Works
Cleveland Road
Hemel Hempstead
Herts.

PROLAPIN Liquid Cement Waterproof
LITHURIN Concrete Floor Hardener
QUICKSocreTE P.Q. & D. Rapid Hardeners and
Setters
WETEXI 'S' Colourless Silicone Waterproof
CONPLAST Concrete Plasticiser
CONPLAST 'W' Anti-freeze and Plasticiser
CEBEX 112 Mortar Improver
CEBEX 113 Expanding Grouting Material
CEBEX 124 Multi-purpose Slurry Liquid
ROAD CONPLAST Air Entrainer and Plasticiser
CONBEX Plasticised Expanding Grouting Material
LIFTOYL Floor Cleaner and Degreaser

CHEMICAL BUILDING PRODUCTS LTD

Telephone: Boxmoor
4900 (5 lines)
Telegrams: Prolithu
Hemel Hempstead

We shall be pleased
to supply full des-
criptive literature.

ORKIT & TEKTAM Bituminous Coatings and
Compounds


CONCURE Concrete Curing Agent
NITOLUX & ROBRITE Paints

NEW! SCREEDEX *The Ideal Screed Additive*

ONE...



TWO!



'STABIL' BINDERS

ARE GREAT LABOUR SAVERS

In one simple action they fix reinforcing rods as though welded. No slipping. No "fiddling" with wire. No tools to get mislaid. Any workman can use them. Made in all sizes for binding $\frac{1}{4}$ -inch up to $1\frac{1}{2}$ -inch rods. Give "Stabil" Binders a trial and judge for yourself.

- SEND TO-DAY for demonstration samples and prices.

HUNTLEY & SPARKS LTD

JAMES ESTATE, WESTERN RD., MITCHAM, SURREY

Phone: MITcham 0121

FLO-MIX

**An Air-entraining
Plasticiser for Mortar**

- Eliminates the use of all lime in Sand—Lime—Cement mortars.
- Increases plasticity and workability.
- Better adhesion is achieved.
- Reduced possibility of cracking and crazing.
- Helps to prevent the penetration of frost into the mortar.
- Recommended for brickwork, pointing, renderings, floor screeds and granolithic toppings.
- Reduces the overall cost of the work.

WHAT IT DOES

When mixed in brick-laying and plastering mortars "Flo-Mix" allows all the lime to be omitted, or the cement content to be reduced, consequently reducing the cost of materials. The plasticity and workability of the mortar are greatly improved and work speeded up. Bricklayers lay more bricks per day, and plasterers can increase the area of rendering carried out. Mortars containing "Flo-Mix" are much more durable than untreated mortars. The mortar is also made rain-proof and is less likely to crack or craze.

Supplied in 5 gall. drums (non-returnable) and 40 gall. drums (returnable). In Liquid form ready for use

Manufactured by:-

ALLIED BUILDING COMMODITIES

QUEENS MILL ROAD, FOLLY HALL

HUDDERSFIELD TEL: HUDDERSFIELD 2901

WOOD MOULDS

for PRECASTING

EXTREME ACCURACY

**ALL
TYPES**

**ALL
SIZES**

25 years' experience at your service

**ARCHITECTURAL SPECIALISTS
AND MODEL MAKERS**

LAWS & SON (STAINES) LTD

(CONTRACTORS TO H.M. GOVERNMENT)

Langley Road Works, Staines, Middx

Telephone: Staines 53700

and

Pottery Lane, Newcastle-on-Tyne

Telephone: Newcastle 20567

for
economy in
bored foundations

DOWN TO 110 FEET

McKINNEY

- * Underreamed
- * Greater bearing area
- * Fewer piles
- * Reduced costs

*May our design engineers assist you with
your foundation problems?*

A **LAING** COMPANY

McKINNEY FOUNDATIONS LIMITED

Manor Way, Boreham Wood, Hertfordshire. Tel: Elstree 2854

Testing concrete cubes on site


MILBANK-WELLS

HYDRAULIC PRESS AND CUBE MOULDS

Immediate Delivery

Two Sizes : 4 in. and 6 in.

PRESSES and CUBE MOULDS
Testing to 16,000 lb. per sq. in. to
B.S. 1001.



Approved for
all Government
Contracts

IN USE
ALL OVER
THE WORLD

6-IN. PRESS
258 TONS

4-IN. PRESS
110 TONS

MILBANK FLOORS LTD

PRESTRESSED CONCRETE CONSTRUCTION

RIVER HOUSE, EARLS COLNE, ESSEX

Telephone: Earls Colne 410




PRESTRESSED FLOORS & ROOFS FRAME BUILDINGS SPANS UP TO 40 ft ALL TYPES



THE MOST ADAPTABLE FRAME BUILDINGS
FOR INDUSTRY AND AGRICULTURE

SINGLE SPAN · MULTI SPAN · CANTILEVER

THE NEW MACALLOY COUPLER



With the new couplers, a force of 55 tons can be provided in a coupled tendon the greatest diameter of which is $1\frac{1}{2}$ ". Coupling boxes to allow the movement of the coupler within the concrete are simple to assemble, inexpensive to produce and quite trouble-free; they can in fact often be used with advantage as grouting check points in very long members.


The coupled joint, like the threaded anchorage, develops 98% of the efficiency of the parent bar and consequently units of unlimited lengths can be developed by fastening a series of bars one upon the other. These bars can be progressively stressed, or the stressing operation can be left until the tendon is complete to its full length.

Couplers are very useful in piled foundations where piles can be extended without any difficulty, when it is necessary to do so because of variation in the depth of penetration. They provide connectors for the mild steel bars when required as anchorage to the pile cap.

When you come to think about it, the coupler provides a simple answer to a multitude of problems which have been waiting a solution of this kind.

The dimensions of these couplers are for:

$1\frac{1}{2}$ " diameter	—	4" long	x	$1\frac{1}{2}$ " O.D.
$1\frac{1}{2}$ " "	—	$3\frac{1}{2}$ " "	x	$1\frac{1}{2}$ " O.D.
1" "	—	3" "	x	$1\frac{1}{2}$ " O.D.
$\frac{7}{8}$ " "	—	$2\frac{1}{2}$ " "	x	$1\frac{1}{2}$ " O.D.




McCALLS MACALLOY LIMITED

TEMPLEBOROUGH • SHEFFIELD • ENGLAND • P.O. BOX 41

Telephone: ROTHERHAM 2076 (P.B. Ex 8 lines)

LONDON: SLOANE 0428 • BIRMINGHAM: ACOCKS GREEN 0229

PORTSMOUTH: COSHAM 78702 • MANCHESTER: BLACKFRIARS 1018



for

COROBAR

REGD TRADE MARK

COLD WORKED HIGH TENSILE REINFORCEMENT

**MILD STEEL &
HIGH TENSILE WELDED FABRIC**

AN EFFICIENT SERVICE ASSURED
IN SUPPLY, BENDING & FIXING

**THE ENGINEERING DESIGN & CONSTRUCTION
COMPANY LIMITED**
REINFORCEMENT SPECIALISTS

OFFICES: ARDSHIEL HOUSE

EMPIRE WAY

WEMBLEY

MIDDX.

TELEPHONE: WEMBLEY 9474

TELEGRAMS: EDCON WEMBLEY



Contractors: Messrs Holst & Co. Ltd.

To render the ground floors in their new warehouse at Grimsby, hard, dustless, waterproof and able to withstand exceptionally heavy wear and tear, British Titan Products Co. Ltd. chose Lillington's No. 1 Metallic Liquid—a veritable titan amongst proofers.

From 5/- per gallon

SPECIAL TERMS FOR BULK CONTRACTORS

Write for Booklet 56

All our products now sold
in free containers

For fifty years, architects have specified Lillington's No. 1 Metallic Liquid, the scientifically prepared admixture that renders concrete completely waterproof and dustless and accelerates setting time.

No. 1 Metallic Liquid is a necessity for waterproofing cement renderings to walls and basements, in mass concrete retaining walls, foundations, flat roofs and tanks. You can rely on it to give complete satisfaction because IT IS THE ONLY PROOFER SOLD UNDER GUARANTEE.

LILLINGTON'S

No. 1 Metallic Liquid

GEORGE LILLINGTON & CO. LTD. WILLOW LANE, MITCHAM, SURREY

Tel: MITcham 1066
C

For Scotland: 42 High Street, Greenock. Tel: Greenock 20175

COPPER STRIPS

for expansion joints

All Reinforced Concrete Engineers recognise the advantages of using copper strips for sealing joints in concrete work. Copper is ductile, will not crack under repeated bending, is non-corrosive and is unaffected by wet concrete. We specialise in the supply of perforated copper strips of all required lengths and widths for expansion joints, and shall be pleased to submit prices against detailed specification.

ALEX J. CHEETHAM LTD.

MORTON STREET • FAIRFORTH • MANCHESTER

Telephone : FAIRFORTH 1115/6



D8.14

Best Quality
**CONCRETE
 AGGREGATES**
in all grades

DELIVERED BY ROAD OR RAIL

**WM. BOYER
 & SONS LTD**

MEMBERS OF S. & G.A. of G.B.

ESTABLISHED 1810

IRONGATE WHARF, PADDINGTON, W.2

TELEPHONE : PADDINGTON 2024-6

"CONCRETE SERIES"

BOOKS ON CONCRETE

For a complete catalogue giving prices in sterling and dollars, send a postcard to :

CONCRETE PUBLICATIONS, Ltd.

14 Dartmouth St., London, S.W.1



Lancaster By-pass JOHNSONS WIRE USED IN BRIDGES and for all roadside fencing!

Johnsons supplied high tensile pre-stressing wire for several of the 24 bridges on the Motorway — another highly successful project in which Johnsons Wire is at work. Sub-contractors for these bridges, Anglian Building Products Ltd. manufacturers of the reinforced and prestressed concrete units, can offer concrete beams up to 120 tons — and they use Johnsons wire.


In addition to the wire used in the bridges, Johnsons also supplied permanent fencing for the complete by-pass. Over 50,000 yards of BULWARK fencing was used together with Johnsons barbed wire and galvanised staples. These Johnsons materials were erected by Durafencing (Northern) Ltd., Fencing Specialists, who carried out the complete roadside fencing project.

For high quality pre-stressing and fencing wire contact


Johnson's

— full specifications immediately available

*The Caton Road Bridge being constructed — one of the bridges which incorporates Johnsons prestressed Wire.
(County Surveyor and Bridgemaister
Mr. James Drake, B.Sc., M.I.C.E.,
M.I.Mun.E., F.Inst.H.E.)*



Richard Johnson & Nephew Limited, Manchester, 11. Tel: East 1431



Circular tipping skips 3) cu. ft. to 3 cu. yd.

ABELSON for SKIPS

ABELSON

& CO. (ENGINEERS) LTD.

SHELDON BIRMINGHAM 26

TELEPHONE : SHELDON 2424 (10 lines)

Special and non-standard skips manufactured to your specifications.



Circular controlled discharge bottom dump skips 1 cu. yd. to 1 cu. yd.


Roller skips 1 cu. yd. capacity.



Concrete pouring skip side discharge 10 cu. ft. to 37 cu. ft.



Boat skips 8 cu. ft. to 7 cu. ft.



Square tunnelling or trenching skips 6-8 ft. cu. ft. capacity.

Concrete pouring skip bottom discharge 10 cu. ft. to 37 cu. ft.



WE ARE SPECIALISTS ★ **WATERTIGHT LININGS FOR RESERVOIRS**
IN THE REPAIR ★ **SWIMMING POOLS, ETC.**
AND RECONDITIONING ★
OF REINFORCED ★ **LININGS FOR TUNNELS**
CONCRETE STRUCTURES ★ **SEWERS**
 ★ **TANKS, ETC.**

GUNITE


CONSTRUCTION CO. LTD

WESTERN HOUSE, HITCHIN, HERTS.

TELEGRAMS:
'GUNITE,
HITCHIN'

TELEPHONE:
HITCHIN 4371

AT LAST—A PORTABLE STRESSING BED AT A SENSIBLE PRICE



IT WILL MAKE—

- FLOOR BEAMS
- LINTELS
- PLANK UNITS
- FENCE POSTS
- RAFTERS
- PURLINS
- BEAMS

YOU CAN—

- MOVE IT
- VIBRATE IT
- STACK IT FOR CURING
(STEAM OR NATURAL)
- USE IT IN FACTORY OR ON
SITE
- USE IT FOR INSTRUCTION
OR RESEARCH

PRICE:

**COMPLETE BED LESS JACKING
EQUIPMENT**

£225.0.0

COMPLETE JACKING SET

£126.0.0

(WILL STRESS ANY NUMBER OF BEDS) Comprising:
2 Hydraulic Rams, 2 Pumps, 2 Pressure Gauges with Flexible
Hoses and Quick-Couplers

Specification:

Construction—All Steel
Capacity—50 tons Max.
For use with—Wire or Strand
Making Area 31 ft. x 3 ft.
Overall Size 33 ft. x 4 ft.
Weight 2,400 lb.

STRESSING DEVELOPMENTS LTD.

95 KINGSTON HILL, KINGSTON-UPON-THAMES 'PHONE: KINGSTON 2372 'GRAMS: STRESS, KINGSTON

GLASS FIBRE

FLOORING

SPIRAL STAIRWAYS

PANELLING

COLUMNS

ALL YOUR MOULD PROBLEMS SOLVED



D. A. MODELS
LTD

108 WOODSTOCK ROAD LONDON W.4
TELEPHONE: CHISWICK 2011

INSEPARABLE from REINFORCEMENT



... OF COURSE!

**and a guarantee that
the specified concrete cover
is accurately maintained . . .**

Complying in ALL respects to the British Standard & Codes of Practice. The U-KLIPON BAR SPACER of revolutionary design is instantly fixed with a vice-like grip in the desired position on all types of reinforcement, including mesh and prefabricated. As an inseparable part it positively cannot be displaced by heavy tamping or vibrating. For any Bar Spacing problem,

CONSULT THE B.E.C. BAR SPACER SERVICE

which has been and is responsible for the most outstanding and prominent contribution to accurate bar spacing in reinforced concrete, thus providing precision, economy, and labour-saving means of ensuring that the specified concrete "cover" is maintained under all conditions. It is noteworthy that such is the increasing popularity and demand for "B.E.C." Bar Spacers, borne out by sales in excess of 35 millions, that we are able to RETAIN OUR PRICE LIST OF 1945 WITHOUT MODIFICATION. Over 120 stock sizes of bar spacers enable us to give immediate attention to requirements. Write now for comprehensive details and samples. Our Technical Consultants will call on request.

Patent Nos. 597,505, 715,563, 789,018, 818,538.

Registered Nos. 870,560, 886,239. English and foreign patents pending.



B.E.C. BEARER BLOCK FOR GROUND BEAMS · BARREL ROOFING BRIDGES · MAT WORK · ETC.

The "B.E.C." precision-made bearer block is another inexpensive B.E.C. aid to obtain accuracy with speed in concrete construction. Let us send you full details.

Enhance your Prestige.
Speedily and use with
confidence.

BERRY'S ENGINEERING CO.

SOLE MANUFACTURERS:

Middle Road, Shoreham-by-Sea, Sussex


Phone and Grams: Shoreham-by-Sea 3541-3

CONTRACTORS TO MINISTRY OF SUPPLY, ETC., ETC.

LENSCRETE LTD

maximum light minimum cost


LITEX roof lights give a very high transmission of light—up to 92%—and are easily and quickly handled and fitted. A full range of standard form metal ventilators, curbs and liners are available for use with LITEX roof lights.

**LITEX spherical roof lights**


Litex

LAMINATED FIBREGLASS
roof lights

LITEX roof lights with their glass fibre reinforced construction can be used with advantage in many places where conventional lights would be impracticable or too costly. Virtually unbreakable, heavy packing is unnecessary allowing quick and easy handling on site.

**LITEX rectangular roof lights**

LITEX roof lights are ideal for use in schools, hospitals and other buildings where absolute safety is required—they will not shatter and cannot support combustion. The plastic will not creep, nor become brittle with age or very hot temperatures.

**LITEX lantern lights**

LITEX roof lights are not attacked by smoke or fumes from most industrial processes, and may safely be used in factory and workshop buildings.

For further information about LITEX roof lights please write to

LENSCRETE LIMITED Queens Circus London SW8 telephone MACaulay 1063



**PUT YOUR FAITH
IN THE TESTED
BRAND**

THIS LABEL ON
EVERY BARREL
CARRIES WITH
IT FIFTY YEARS'
EXPERIENCE OF
MANUFACTURE.

**NONE OTHER IS
"JUST AS GOOD"**

THE LEEDS OIL & GREASE CO.

Phone 22480

LEEDS, 10 'Grams: "Grease, Leeds 10"

STEEL REINFORCEMENT



ALL DIAMETERS

**WE OFFER A
COMPLETE SERVICE
OF DESIGN, SUPPLY,
CUT, BEND, LABEL,
DELIVER & FIX**

Let us have your specification for all or any part of these services & we will quote you our competitive prices delivered works or site.

Write,
telephone or telex
your requirements

WELBECK

(STEEL STOCKHOLDERS) LTD

STEEL WHARF, RIVER ROAD,
BARKING, ESSEX

Telephone: R1Ppleway 5751-4

Telegraphic add: Steelwarf, Barking, Telex.
Telex: 21194




Illustration above shows some of the post-stressed bridge beams, each 80 ft. long and weighing 35 tons, produced by Anglian Building Products Ltd., for British Railways, Midland Region. Main Contractors: Messrs. Leonard Fairclough Ltd.

80 - ft. BEAMS cast in WOODEN MOULDS

supplied by

MAY & BUTCHER LTD

SPECIALISTS IN TIMBER SHUTTERS AND MOULDS FOR CONCRETE

More and more Contractors and Precast Concrete Makers in all parts of the country are taking advantage of the first-class service we offer in the supply of timber shutters and moulds to any design and size. This service has proved over and over again that by ordering your shutters and moulds from us you effect every possible saving in time, labour and money. However intricate the shutter or mould, you are assured of accuracy in every detail and a product with long trouble-free life. Shutters and moulds can be supplied with a plastic lining if desired. Full details of this class of work carried out by us are available on request.

HEYBRIDGE BASIN, MALDON, ESSEX.

TELEPHONE: MALDON 698/9

TODAY'S MOST ACCURATE, SPEEDY AND ECONOMICAL SYSTEM OF CONCRETE PREPARATION



"ELBA"

Ground-level aggregate weighing & batching plants



**1 "ON THE JOB" AGGREGATE STOCKPILING,
CONTINUOUS HANDSCRAPER FEEDING**
... star compartments for 3 to 5 aggregates

2 REMOTE CONTROL OPERATION
... "one man" operated lever system

3 ACCURATE WEIGHING
... clear view weigh dial

**4 DIRECT FEEDING OF CEMENT
INTO MIXER PAN**
... high-angle cement screw weigher

5 HIGH-OUTPUT, QUALITY CONCRETE
... "rotor-forced" "Walmer" mixer

6 CONCRETE STORAGE
... remotely controlled hopper

SEE US AT CRYSTAL PALACE
STAND A88

Model 10000 Series by A.C.E. Ltd. - Division of Messrs. Buxton

A.C.E. MACHINERY LIMITED · PORDEN ROAD · BRIXTON · LONDON · S.W.2

Telephone: BRIXTON 3293 (9 lines) Telegrams: Auscon Telex 23579 LONDON

GUNITE SPECIALISTS

**WM. MULCASTER
& CO. (CONTRACTORS) LTD.**

We invite inquiries for Gunité Linings and Renderings
for new or old structures of every kind in any part
of the country.

HASLINGTON

Telephone : Crewe 2265-6

CREWE

*Ensure
safety
with*

**DORMAN
LONG Steel Trench Sheeting**
(Regd. Design No. 850,839)

**The ideal for temporary lining,
easy to drive: can be used over and over again**

PROMPT DELIVERY *Prices and full particulars on application to*

DORMAN LONG (Steel) LTD., SHEET DEPT., AYRTON WORKS, MIDDLESBROUGH
London Office: Terminal House, 52 Grosvenor Gardens, S.W.1



THE WORLD'S LONGEST SUBMERSIBLE BRIDGE



Colcrete GROUTED CONCRETE in BRIDGE CONSTRUCTION

Work has recently been completed on this 2,434 ft. long reinforced concrete bridge which carries the Bombay—Agra road between Gwalior and Dholpur over the River Chambal. The bridge is 24 ft. wide between kerbs.


Colcrete was used for the foundations, piers and the fill over the spandrels.

The Contractors were Messrs. Gammon India Private Limited.

COLCRETE LIMITED

STROOD • ROCHESTER • KENT

Phone Strood 78431/2/3. Grams : Groutcrete, Rochester



THE P.C.4 PUMPCRET CONCRETE PUMP

CONCRETE BY PUMP AND PIPELINE

Specifications:

Two Sizes	P.C.3	P.C.4
Capacities per hour, approx. . . .	20-24 cu. yd.	8-10 cu. yd.
Range:		
Horizontal, approx.	1500 ft.	1250 ft.
or Vertical, approx.	135 ft.	125 ft.
Pipeline	6" i.d.	4½" i.d.
Power required: Electric or Diesel	45 h.p.	25 h.p.

FOR HIRE



THE REGISTERED TRADE MARK OF
THE CONCRETE PUMP COMPANY LIMITED


PUMPCRET HIRE COMPANY LTD

4 STAFFORD TERRACE, LONDON, W.8

Telephone: Western 3546.

Telegrams: Pumpcret, Kens, London

SINEX TURBO PNEUMATIC IMMERSION VIBRATORS



The most powerful vibrators of their kind in the world

The amazing Sinex Turbo-Pneumatic Immersion Vibrators contain no bearings and have only two air-cushioned moving parts. The four types available fulfil every need in achieving speedy and efficient concrete compaction. The smallest vibrator with a diameter of only $1\frac{1}{4}$ inches is ideal for use where close reinforcement is encountered.

The Sinex range of immersion vibrators has the world's largest sale, proof of its long life, negligible maintenance costs and freedom from breakdowns.

Write for illustrated leaflet



**SINEX
EXTERNAL VIBRATORS**
available in two sizes, are
ideal for use on shuttering,
moulds and tables.

Stocked and Serviced by

E. P. ALLAM & CO. LTD.

132/135 SLOANE STREET, LONDON, S.W.1.

Tel: SLOANE 9976 (5 lines)


Telegraphic Address: EPALTRICAL, KNIGHTS, LONDON.

London Stores & Service Depot:

CORNETTS PASSAGE • SILWOOD STREET • LONDON, S.E.18. Tel. BERNBORSEY 4289

Works:

ARTERIAL ROAD • EASTWOOD • LEIGH-ON-SEA • ESSEX. Tel. EASTWOOD 525343



A Member of the




Group

Agents at:-

Port Talbot, Glam.
Altrincham, Cheshire.
Burslem, Stoke on Trent.
Weatherby, Yorks.
Glasgow, C.S.

Dublin.

Newcastle upon Tyne 1
Belfast, Northern Ireland.
Oldbury, Birmingham.



from every aspect, the finest equipment

**FOR SITE
HANDLING
OF BULK
CEMENT**

PORTASILS LIMITED • Home Sales Office:
LAWRENCE ROAD • GREEN LANE • BURNSTOWN • MIDDLESEX
Telephone: Hounslow 6452/3

HEAD OFFICE: LONDON • BRANCHES: BIRMINGHAM • MANCHESTER
GLASGOW • BRISTOL • BELFAST and DUBLIN

*Write or phone today
for details of full range
of equipment*

CONCRETE AND CONSTRUCTIONAL ENGINEERING

INCLUDING PRESTRESSED CONCRETE

Volume LVI, No. 6.

LONDON, JUNE, 1961.

EDITORIAL NOTES

Speed of Construction.

A FEATURE of current civil engineering works and buildings in Great Britain is in many cases the greater speed of construction compared with that common a few years ago and, in some instances, compared with the general rate in pre-war years. That the productivity of the constructional industries is increasing is borne out by statistics issued by the Ministry of Works which show that production, which in 1959 was 11 per cent. more than in 1954, was 18 per cent. more in 1960. This increase unaccompanied by a proportionate increase in manpower is in part due to the more extensive use of mechanical aids to construction and in part due to the greater attention given to the planning of the work before work on the site commences. The extent to which mechanisation is used on constructional sites is shown by the fact that it is estimated that up to 1914 the horsepower per man was less than five whereas on motorway M1 it was about twenty and on the construction of the new Spencer Steelworks at Llanwern, Mon., which is claimed to be the largest civil engineering contract ever placed in Great Britain with one firm, the equipment is rated at about 27 h.p. per man.

Speed of construction is not unrelated to cost. One form of construction may be more expensive than another but the extra cost may be offset by financial savings or gains resulting from the shorter time taken to erect the structure. But if greater speed of construction is allied to the cheaper form of construction, then obviously that form is the most advantageous. In a survey, made recently by the Reinforced Concrete Association, of nine reinforced concrete multiple-storey buildings in various parts of Great Britain, it is established that the average time to construct a floor was fifteen days or less, and the average rate for each of the floors above the second floor was twelve days or less. Generally office buildings were in the higher range (that is, more than a working week for each storey), while residential buildings were among the lower range, some such structures requiring one to two days only for each floor. There appears to be reliable documentary evidence that there is at present a saving of from five to ten per cent. of the total cost of a building, and at least twenty per cent. of the cost of the structural frame, if constructed in structural concrete compared with steelwork encased in concrete.

However, the average rate of construction for each floor of a building may not

be a measure of the overall time of construction of a complete building as it is well known that the foundations and other operations preliminary to the construction of the superstructure and, more particularly, the finishing operations protract considerably the period before a building can be put into use. Although the frame and floors of an eleven-storey building in London was constructed in eighteen weeks, the building took ten months in all to complete; nevertheless a good performance. Another noteworthy example of overall speedy construction was a new eighteen-storey hotel in London, which cost about £2,000,000 and gained commendation by the American owners since the work was completed in appreciably less time than they would expect it to take in the U.S.A. In fact this building, which is one of the tallest residential structures in London and the volume of which is about 2,500,000 cu. ft. and which contains about 13,500 cu. yd. of concrete, was constructed in eighteen months, that is at the overall average rate of a storey per month, although the actual rate per floor was considerably less than this. The overall time was said to be six months less than the scheduled period. An office building in London also comprising in part eighteen storeys was also erected in eighteen months. Other examples have been given in this journal.

Comparison of estimated and actual times of construction may not always be valid because the reason for the latter being the shorter may be that the estimated time was unduly pessimistic or that the amount of time lost by bad weather was less than expected. There are cases, however, in which comparative times are valid because of speeding up of operations due to good design and planning or mechanisation; or it may be because a special method of construction is adopted, as in the construction of the trial tunnels of the proposed Victoria-Walthamstow tube railway, which is described elsewhere in this number and for which the rate of boring and lining was twice that of similar tunnels constructed by the methods used before the war. Other methods, such as constructing the minimum amount of foundations to support the dead load of the structure or of the lower floors only so that construction of the upper floors and finishing operations can proceed while the basement and foundations are being completed, or construction by the lift-slab method by which delays by inclement weather are largely avoided, or construction completely or partially of precast concrete are some of the means whereby work on the site is accelerated. Or more unusual methods may be adopted as in the case of a departmental store in Glasgow in which, after the erection of the frame, the roof and then the upper floors were constructed successively from the top downwards while construction of the lower floors proceeded successively upwards.

The effect of design on the speed of construction was the subject of a lecture organised by the National Federation of Building Trade Employers and given last autumn to the Royal Institute of British Architects by a representative of a well-known firm of contractors. It was stated that the architect exerts considerable influence on the constructional time by virtue of the wide choice of materials and designs available, but any potential saving of time due to a well selected design can be offset by delays in the receipt of information on the site. Standardisation of the sizes of structural parts, whereby the greatest number of uses of the shuttering is obtainable, is desirable; the total time lost in altering shuttering may add from four to eight weeks to the constructional time of a multiple-storey building. It was stated that the speed of construction of a reinforced concrete

frame is determined by the shuttering gang rather than by the concretors. While in this country drier mixtures of concrete tend to be used, with accompanying increase in the difficulty of placing, practice in the U.S.A. seems to favour concrete in superstructures having a slump of 3½ in. to 5 in., which may expedite placing, but nevertheless the time spent on the substructure and superstructure is in general much the same in both countries. The saving in time in the U.S.A. is generally on the cladding and finishes which may be a little more austere than is usual in Great Britain.

Precasting can do much to accelerate construction if the parts are cast sufficiently in advance of the requirements on the site, and some creditable performances have been recorded. There is the case of a small laundry building, the precast frame of which was erected within eight days of the receipt of the order, the entire building taking eleven weeks. At a factory near Liverpool, which cost £2,000,000 and was built in twelve months, one building 123 ft. wide incorporated precast frames the erection of which commenced six weeks after placing the order and proceeded at an average rate of three bays (including the roof) each week, the maximum rate being five bays per week. Such performances, good as they are, do not compare with what is probably the record, namely the erection in 1959 of a five-storey block of flats in France. The cast-in-situ foundations were constructed within a month; nine days later the superstructure, which comprised large precast elements, was completed; the tenants were in occupation of the building within eight weeks from the start of building operations.

Design of Reinforced Concrete Members.

METHODS of designing and analysing reinforced concrete members are very numerous and it may be thought that there is no new manner of presenting aids to rapid design. In this number is given the first of a series of articles describing a method which can claim to be most comprehensive in so far that it applies to members of any cross-section, whether subjected to direct force or simple bending, or to bending combined with direct force. The basis is in accordance with the elastic (modular-ratio) or load-factor methods and is applicable whether the design has to comply with the British Standard Code, the Code of the American Concrete Institute, or similar regulations whatever, in the case of load-factor methods, the load factor may be.

The principle is that the resistance of members of any cross-section can be determined by the same procedure of computation by introducing non-dimensional factors relating to the shape, applied moment and direct force, and stresses. In the series of articles it is assumed that the section has an axis of symmetry in the plane of the load, and that the tensile strength of the concrete is ignored. Only cases where compressive and tensile stresses are developed simultaneously are considered. The method is developed for a general form of distribution of compressive stress in the concrete and is then applied in detail to the particular distributions assumed in the elastic and the load-factor theories. The method is readily applied by means of nomograms of non-dimensional form with all the quantities involved considered as variables, enabling designers to carry out accurate calculations easily and rapidly. The application of the method and the use of nomograms is illustrated by reference to a general trapezoidal section, particular cases of which are rectangular and triangular sections but nomograms for members of other cross-sections and for the case where the concrete is effective in tension and where the stresses are compressive only have been prepared.

In presenting charts, the form likely to be accepted by designers should be considered but, as has been pointed out before in this journal, nomograms have unique features when more than three parameters are involved.

Book Reviews.

"Frames and Arches". By V. Leonovich. (London: McGraw-Hill Publishing Co., Ltd. 1959. £7 15s.)

This is an important book and should be of considerable practical aid to the designer of indeterminate structures. To quote from the foreword contributed by Prof. S. P. Timoshenko: "This book is a considerable step forward in applied structural engineering. Its contents are selected to facilitate practical design of rigid frames and arches. For the first time, a solution for analysis of frames with members of variable cross-section, based on the classical method, is presented in a convenient practical form. All computations with this method are confined to simple, short operations; the time required for frame analysis is greatly reduced. Another important feature of the book is a new solution of frames with members of constant cross-section. Since the author's method is substantially shorter than any other in current practice, his approach should, no doubt, be favoured by designers."

These claims are not extravagant. Comparisons with the better-known "Kleinlogel" are unavoidable since the formulae are presented in a very similar manner. The book under review is limited to structures of one bay or span, and to frames the two legs of which are of the same length, and in these respects is not so fully comprehensive. It does, however, include frames each member of which is of non-uniform cross-section and, more importantly, frames with haunches or plays in the corners. The shapes of the hinged and fixed frames dealt with are rectangular portal frames with straight and parabolic beams, trapezoidal frames and gable frames. The consideration of arches is limited to fixed and two-hinged parabolic forms.

"A Guide to the B.S. Code of Practice for Prestressed Concrete." By F. Walley and S. C. C. Bate. (London: Concrete Publications, Ltd. 1961. Price 12s. 6d.; by post 13s. In Canada and U.S.A. 3 dollars.)

This book provides an informed commentary on the British Standard Code of Practice CP. 115 (1959), "The Structural Use of Prestressed Concrete in Buildings",

since the authors were prominent members of the committee responsible for the compilation of the Code. The Code is given in full and the comments and explanations follow each clause. Recommendations relating to aspects of prestressed concrete construction which are not common to other forms of concrete construction are in particular amplified. The subject matter is dealt with under the same headings as in the Code, namely definitions and symbols, materials, design stresses, the design of structural members subjected to pure bending or direct compression, fire resistance, methods of prestressing, practical considerations, inspection and testing. A concise bibliography is given and there are twelve tables in addition to those in the Code, and twelve diagrams or charts containing valuable data for the designer particularly in respect of eccentrically-loaded members. The commentaries on steel for prestressing, stresses, loss of prestress, resistance to shearing, the ultimate resistance of beams, and fire resistance are noteworthy in respect to their length and content.

"Building Construction Estimating."

By G. H. Cooper. (London: McGraw-Hill Publishing Co. Ltd. 1959. Price 60s.)

This second edition of an American book on the subject of cost estimating for buildings is an enlargement of the preceding edition. It is essentially a textbook for students learning the principles of the subject rather than a guide giving prices and data for a contractor's estimator. It is therefore of value to students other than those concerned solely with American practice. The scope of treatment is limited mainly to house building and therefore reinforced concrete and allied methods of construction are not dealt with fully except in so far that foundations, floors, and walls are built of concrete. The range of topics is quite wide, extending as it does from the relations between architect, contractor and client to the commercial sizes of nails. Some interesting sidelights are also included such as the diagram illustrating how a tree is sawn to provide timber for various constructional purposes.

A Practical Comprehensive Method of Designing Reinforced Concrete Sections.—I.

By J. RYGOL, B.Sc.(Eng.).

WHEN designing or analysing reinforced concrete sections of various shapes the use of a method of computation, which is applicable to axial or eccentric compression or tension, and simple bending, and is in accordance with the elastic and the load-factor methods, is advantageous. Such a method is described in these articles. (See Editorial Note on page 207.)

The problem involves the consideration of three interrelated factors (Fig. 1), namely (a) the details of the section, (b) the loading, and (c) the stresses developed in the section when subjected to the loading. The principal dimensional quantities which describe these factors are interrelated in one set of basic equations using non-dimensional factors referred to as stress-factors. The general equations of equilibrium of the internal stresses and the external loading are then expressed in non-dimensional form in terms of the stress-factors, and these equations are referred to as the stress-factor equations.

DIMENSIONAL QUANTITIES.

Section.

- d = effective depth; h = overall depth; l = depth dimension.
- b = reference breadth; b_0 = breadth dimension.
- x = depth to neutral axis.
- a = depth of equivalent rectangular stress block at ultimate load.
- g, g' = concrete cover of tension and compression reinforcement respectively.
- A_s, A_s' = cross-sectional area of tension and compression reinforcement respectively.
- I = moment of inertia of transformed concrete section.
- A_c = cross-sectional area of concrete in compression.




Fig. 1.

Loading.

N = applied normal force (compressive or tensile).

$N_u = kN$ = ultimate normal force.

e_t, e_c = eccentricity of N (or N_u) measured from centroid of tension and compression reinforcement respectively.

$M_t = Ne_t; M_c = Ne_c$.

$M = M_t = M_c$ = applied bending moment when $N = 0$.

ΔM_t = unbalanced part of bending moment M_t in $M_t = \bar{M}_t + \Delta M_t$.

$M_{ut}(= N_ue_t), M_{uc}(= N_ue_c), M_u(M_{ut} = M_{uc}),$ and $\Delta M_{ut}(= M_{ut} - \bar{M}_{ut})$
= values of $M_t, M_c, M,$ and ΔM_t respectively at ultimate load.

Stresses and Strains.

f_c = maximum compressive stress in concrete (elastic).

f_s, f'_s = stress in steel at centroid of tension and compression reinforcement respectively (elastic).

f_u = uniform stress in concrete of equivalent rectangular stress-block at ultimate load.

f_y, f'_y = yield-point stress of tension and compression reinforcement respectively.

u, u_{cyl}, u_{pr} = 28 days' strength of 6-in. concrete cubes, 6-in. by 12-in. cylinders, and prisms, respectively.

D_c = resultant of compressive stresses in concrete.

D_{cu} = resultant of compressive stresses in concrete at ultimate load.

E_s, E_c = modulus of elasticity of steel and concrete respectively.

ϵ_c = maximum compression strain of concrete (elastic).

ϵ_s, ϵ'_s = strain (elastic) in tension and compression reinforcement respectively.

ϵ_u = maximum compressive strain of concrete at ultimate load.

ϵ_y, ϵ'_y = yield strain of tension and compression reinforcement respectively.

*NON-DIMENSIONAL RATIOS.**Section.*

$\delta = t/d$ = depth-ratio; $\gamma = b_o/b$ = breadth-ratio; $n = x/d$ = neutral-axis depth-ratio.

$\alpha = a/d$ = depth-ratio of equivalent rectangular stress block at ultimate load.

$\beta = g/d, \beta' = g'/d$ = embedment-ratio of tension and compression reinforcement respectively.

$r = A_c/(bd)$ = shape coefficient.

$p = A_s/(bd), p' = A'_s/(bd)$ = tension and compression reinforcement-ratio respectively.

$\lambda = x/d, \lambda' = x'/d$ = lever-arm depth-ratios.

$\mu = I/(bd^3)$ = moment of inertia coefficient.

Loading.

$k = N_u/N$ = load factor.

$\epsilon = e_t/d; \epsilon' = e_c/d$ = eccentricity ratios.


Stresses.

$q = p \frac{f_s}{f_c}$ = tension reinforcement-index (elastic), $= p \frac{f_s}{f_u}$ at ultimate load, if not controlled by yielding of tension reinforcement.

$q' = p' \frac{f'_s}{f_c}$ = compression reinforcement-index (elastic), $= p' \frac{f'_s}{f_u}$ at ultimate load, if not controlled by yielding of compression reinforcement.

$q_y = p \frac{f_y}{f_u}$ = tension reinforcement-index at ultimate load if controlled by yielding of tension reinforcement.

$q'_y = p' \frac{f'_y}{f_u}$ = compression reinforcement-index at ultimate load if controlled by yielding of compression reinforcement.



SECTION

Fig. 2.




Fig. 3.

$r = \frac{f_s}{f_c}$ = stress-ratio (elastic); $r_y = \frac{f_y}{f_u}$ = stress-ratio at ultimate load.
 $m = E_s/E_c$ = modular ratio; $m_u = (E_s e_u)/f_u$ = plastic modular ratio at ultimate load.

NON-DIMENSIONAL FACTORS.

- $\kappa_1, \kappa_2, \kappa_3$ = stress-block factors.
- $\kappa_{1u}, \kappa_{2u}, \kappa_{3u}$ = stress-block factors at ultimate load.
- ϕ_1, ϕ_2, ϕ_3 = shape factors.
- K_c, K_s = concrete and steel stress-factor respectively for normal force N .
- C_t, S_t = concrete and steel stress-factor respectively for moment of N about centroid of tension reinforcement.
- C_c, S_c = concrete and steel stress-factor respectively for moment of N about centroid of compression reinforcement.
- K_u, C_{tu}, C_{cu} = values of K_c, C_t , and C_c respectively at ultimate load.

Basic Ratios.

Shape of Section.—A reinforced concrete section (Fig. 2) is described completely by the dimensions of the section and the amount and location of the reinforcement. The classification of sections is made according to the shape of the compression zone of concrete. The shape of the concrete section in the tension zone is generally of no importance as the tensile strength of concrete is ignored. The principal dimensions of a section are the effective depth d , measured from the extreme edge in compression to the centroid of tension reinforcement, and a freely chosen reference breadth b . The shape of the compression zone is

described by depth dimensions t (measured from the same extreme edge in compression) and breadth dimensions b_0 . These dimensions can be expressed in non-dimensional form by reference to the principal dimensions d and b as ratios $\delta = t/d$ and $\gamma = b_0/b$. The reference breadth b and the dimensions t and b_0 are practical choices; for example, for a rectangular section the reference breadth b is the actual breadth of the section, and, as there is no variation in depth or breadth of the section, $\delta = 0$ and $\gamma = 0$; for a T-section the breadth of the flange is taken as the reference breadth b , the thickness of flange as t , and the breadth of the rib as b_0 , so that $\delta (= t/d)$ is the ratio of depth of the flange to the effective depth and $\gamma (= b_0/b)$ is the ratio of breadth of the rib to breadth of the flange.

The cross-sectional areas of the reinforcement in tension and compression are denoted by A_s and A_s' respectively. In the general case of eccentric loading, A_s denotes the cross-sectional area of the reinforcement near the edge farther from N if N is a compressive force, and nearer to N if N is a tensile force. Similarly, A_s' denotes the reinforcement along the edge nearer to N if N is a compressive force, and farther from N if N is a tensile force.

The distance from the centroid of the reinforcement to the nearest edge of the section is denoted by g when referring to A_s , and g' when referring to A_s' . The dimensions g and g' are expressed in non-dimensional form as $\beta = g/d$ and $\beta' = g'/d$. The cross-sectional areas of reinforcement are expressed in non-dimensional form as $p = A_s/(bd)$ and $p' = A_s'/(bd)$.

Loading.—In the general case the section is subjected to a normal force N , compressive as in Fig. 3a, or tensile as in Fig. 3b, acting at an eccentricity e if measured from the mid-axis of the section, and e_t and e_c if measured from the centroids of the tension and compression reinforcements respectively. The moments of N about the tension and compression reinforcements are $M_t = Ne_t$ and $M_c = Ne_c$. The eccentricities e , e_t , and e_c are expressed as ratios of the effective depth by $e_0 = e/d$, $e = e_t/d$, and $e' = e_c/d$. Simple bending




Fig. 4.




Fig. 5.




Fig. 6.

(Note.— $q_b = \bar{q}_b$.)

($M = M_t = M_c$) as in Fig. 3c is a particular case of eccentric loading when $e = e_t = e_c = \infty$. At ultimate load, the normal force is N_u , and the moments of N_u about the centroids of tension and compression reinforcement are M_{ut} and M_{uc} respectively.

Stresses.—In the general case the distribution of stress in the compression zone is curvilinear (Fig. 4a). The principal stresses are the compressive stress f_c at the extreme edge, and the stress f_s in the tension reinforcement. The stress in the compression reinforcement is f_s' . The ratio of f_s to f_c is denoted by r , and the ratio of f_s' to f_c by r' . At ultimate load the compressive stress in the concrete is f_u and the stress in the tension reinforcement attains usually the yield-point stress f_y (f_y' in the compression reinforcement); hence $r_y = f_y/f_u$ and $r_y' = f_y'/f_u$.

Strains.—Plane sections before loading are assumed to remain plane after loading (Fig. 4b), that is, the strain at any element of the section is proportional to the distance of the element from the neutral axis. The strain at the extreme edge in compression is ϵ_c , in the tension reinforcement ϵ_s , and in the compression reinforcement ϵ_s' . At ultimate load the maximum strain of the concrete is ϵ_{cu} , in the tension reinforcement ϵ_y , and in the compression reinforcement ϵ_y' if controlled by yielding of the steel.

Basic Equations and Factors.

The basic equations, expressed in terms of the concrete stress f_c , are

$$N = K_c f_c b d, \quad . \quad . \quad . \quad . \quad . \quad (1)$$

$$M_t = N e_t = C_t f_c b d^2, \quad . \quad . \quad . \quad . \quad . \quad (2)$$

$$M_c = N e_c = C_c f_c b d^2, \quad . \quad . \quad . \quad . \quad . \quad (3)$$

where K_c , C_t , and C_c are the stress-factors. The sign convention in respect of N is as follows. In equation (1) N is positive if it is compressive and is negative if tensile; hence K_c is positive if N is compressive and negative if N is tensile. In equations (2) and (3) N is entered at its numerical value; the eccentricity e_c is negative if the line of action of N is between A_s' and A_s , and positive if outside.

As the equilibrium between the internal stresses in the section and the external loading is described completely by two equations, it follows that only two

of the three basic equations are independent, the interrelation being

$$N = \frac{M_t - M_c}{d - g'} \quad \text{and} \quad K_e = \frac{C_t - C_c}{1 - \beta'}.$$

Compressive Stress-block.—The general form of the distribution of the compressive stress in the concrete is shown in Fig. 5, where D_c is the resultant compressive force in the concrete acting at distances $z (= \lambda d)$ and $z' (= \lambda' d)$ from the centroids of the tension and compression reinforcement respectively. The properties of the stress-block are described by the non-dimensional stress-block factors κ_1 , κ_2 , and κ_3 as follows.

$$D_c = \kappa_1 f_c b d. \quad (4)$$

The moment of D_c about the centroid of tension reinforcement is

$$z D_c = \kappa_2 f_c b d^2. \quad (5)$$

The moment of D_c about the centroid of compression reinforcement is

$$z' D_c = \kappa_3 f_c b d^2. \quad (6)$$

The relation between the factors κ_1 , κ_2 , and κ_3 is

$$\kappa_1 = \frac{\kappa_2 + \kappa_3}{1 - \beta'}. \quad (7)$$

Thus the lever-arm depth-ratios of D_c about the centroid of tension and compression reinforcement respectively are

$$\lambda = \frac{\kappa_2}{\kappa_1} \quad \text{and} \quad \lambda' = \frac{\kappa_3}{\kappa_1}.$$

Stress-factor Equations.—The stress-factor equations describe in non-dimensional form the equilibrium conditions between the internal stresses and the external loading, and are

$$K_e = \kappa_1 + q' - q, \quad (8)$$

$$C_t = \kappa_2 + (1 - \beta')q', \quad (9)$$

$$C_c = -\kappa_3 + (1 - \beta')q, \quad (10)$$

where $q = pr$ and $q' = p'r'$, which are the tension reinforcement-index and the compression reinforcement-index respectively.

Simple Bending.—For simple bending $N = 0$ and $M_t = M_c = M$; hence $K_e = 0$ and $C_t = C_c = C$, and the equation (8) becomes

$$\kappa_1 + q_b' - q_b = 0$$

in which the subscript b indicates that the relationship is applicable to simple bending only.

Section Reinforced for Tension Only.—Since $q' = 0$, $K_e = \kappa_1 - \bar{q}$, and $C_t = \kappa_2$. Therefore

$$N = K_e f_c b d, \quad (11)$$

$$\bar{M}_t = N e_t = C_t f_c b d^2, \quad (12)$$

where K_e , C_t , \bar{q} , and \bar{M}_t refer to a section reinforced for tension only.

Section Reinforced for Tension and Compression.—The values of q and q' can be computed from

$$q' = \frac{C_t - \bar{C}_t}{1 - \beta'} \quad \text{and} \quad q = \bar{q}_b + q' - K_e,$$

where $\bar{q}_b (= \kappa_1)$ is the tension reinforcement-index of the section, with the same stress-block, reinforced for tension only to resist a bending moment \bar{M}_t . Note that $M_t = \bar{M}_t + \Delta M_t$ and $C_t = \bar{C}_t + \Delta C_t$.

The expediency of using the foregoing relations is illustrated in Fig. 6 which shows how the calculation of reinforcement for a section reinforced for tension and compression can be reduced to the much simpler calculation of (i) \bar{q}_b as for a section subjected to a bending moment \bar{M}_t ; (ii) q' resisting ΔM_t ; and (iii) K_e resisting N applied at the centroid of the tension reinforcement.

Sizewell Nuclear Power Station.

CONSTRUCTION began in April last of the nuclear power-station at Sizewell, Suffolk, for the Central Electricity Generating Board. This station will be the largest under construction in the world since, on completion in 1966, the capacity will be 580 megawatts. It is claimed that it will also be the most compact station, and it will be the first to have two reactors installed in a composite building. Some notes on, and an illustration of, the station are given in this journal for January 1961.

The 400-ton Goliath crane at the nuclear power-station at Hinkley Point is to be removed and re-erected at Sizewell early next year. There will also be two 7-ton ground-derricks with 120-ft. jibs. Gabbard-derricks and tower-cranes will be used in the construction of the biological shields and the superstructure of the reactor building. Construction of the foundations involves more than 500,000 cu. yd. of excavation. It is expected that the concrete batching and mixing plants will produce concrete at a rate of up to 4000 cu. yd. weekly.

To minimize differential settlement, comparable operations on the two reactors will take place within a short interval of time. The foundations of the reactors will be a reinforced concrete raft 225 ft. long and 110 ft. wide, and will be constructed in a series of lifts and bays, and will require the excavation of 17,000 cu. yd. of sand and the placing of 140,000 cu. yd. of concrete. The superstructure of the reactor building will be 193 ft. high and 400 ft. long. The primary biological shield-walls around the pressure vessels

will be duodecagonal on plan, and will be of concrete 6 ft. thick and will be more than 86 ft. high above the foundations.

The foundations of the turbine house will be deeper than those of the reactors, and will require excavation to a maximum depth of 35 ft. About 140,000 cu. yd. of sand will be excavated and about 130,000 cu. yd. of concrete is to be placed below ground level. An extensive dewatering system will be required to lower and control the ground water.

The cooling-water intake will be 1800 ft. off-shore and sea-water will be drawn through this installation at the rate of over 27,000,000 gallons an hour. After use the water will be discharged at a point 500 ft. off-shore. Four tunnels of 10 ft. diameter will be driven in compressed air in connection with the off-shore works. A major dewatering scheme will be required for constructing the cooling-water pumphouse and access shaft to the tunnels. Excavations will extend to a depth of about 70 ft. and the water-table will be lowered by about 40 ft. The access shaft will be formed within a cofferdam of steel sheet-piles. The excavation for the pumphouse will be carried out within a system of open-cut excavations and steel sheet-piles. Tests of alternative procedures of sheet-piling have been carried out to determine the optimum method for driving the piles.

The labour force is expected to be about 2400 in 1962. The station is being constructed by the Atomic Power Group comprising The English Electric Co., Ltd., Messrs. Babcock & Wilcox Ltd., and Taylor Woodrow Construction Co., Ltd.



Fig. 1.

(See facing page.)

A Concrete-lined Tube-railway Tunnel.

SOME experimental tunnels for tube railways are being constructed by London Transport in north London. One of the objects of the work is to enable experience of new methods of tunnel construction to be obtained prior to the commencement of the construction of the new tube railway from Victoria to Walthamstow; the experimental tunnels are on the alignment of the new railway and will be incorporated therein. The new railway will be 11½ miles long. The experimental tunnels comprise a mile length of double tunnel extending from Finsbury Park to Nether-ton Road, Tottenham. Another object is to determine whether cast iron segments or precast concrete are more suitable for lining tunnels bored in London clay by a new type of machine. The linings are not bolted or grouted. About ½ mile of double tunnel with cast-iron segments and a ½ mile of single tunnel with concrete blocks (*Fig. 1*) have been completed. A feature of the work is that tunnelling proceeds at about twice the rate attained by methods previously used.

Excavation.

The tunnels are being bored by a type of rotary shield called a "drum digger", which can work much faster than any previous type of shield used for tube-railway construction in London and which makes provision for belt-conveyors to remove the spoil.

There are working sites and shafts at the corner of Nether-ton Road and Seven Sisters Road (Tottenham), and in Finsbury Park. The shaft at Nether-ton Road is 25 ft. in diameter and 60 ft. deep, and will be a permanent part of the new railway since it will be used for ventilation and emergency stairs. From the bottom of the shaft an access tunnel extends a short distance to the line of the rail tunnels, where chambers large enough to permit the assembly of the rotary shields have been excavated by pneumatic spades and lined with bolted cast-iron segments. At this site, excavated spoil is brought to the surface by a crane which lifts 1½-cu. yd. skips off the 2-ft. gauge bogies which have brought the spoil, in trains hauled by battery locomotives, along the completed section of the tunnels. The skips are

loaded by belt-conveyors fed from the rotary cutters at the working face, and are emptied on to the ground at the surface, where the spoil is loaded into lorries by a 1-cu. yd. mobile shovel.

At the Finsbury Park site, the shaft is 15 ft. in diameter and 60 ft. deep. As at the other site, an access tunnel leads from the bottom of the shaft to the rail tunnels, and there are two chambers in which the shields are assembled. The rail tunnels are on a gradient of 1 in 47 and the loaded ¾-cu. yd. skips are hauled by an electric winch located in the shield-assembly chamber. The spoil is tipped from the skips on to a belt-conveyor in the access tunnel and the conveyor delivers the spoil to the bottom of the shaft, where it is raised to the surface by a vertical bucket-elevator. The buckets are warmed by hot air to prevent the clay from sticking to the metal. Originally, the clay was deposited in an elevated hopper under which lorries could be loaded by gravity, but because of the rate of excavation it is necessary to deposit the spoil on the ground and use a 1-cu. yd. mobile shovel for loading.

The "drum-digger" type of shield is the same as that used previously on the tunnel from Hampton to Chingford for the Metropolitan Water Board (see this journal for April, 1960), but the experimental railway tunnels are larger than the water tunnel, and the shield is therefore also larger. The "drum-digger" for the concrete-lined tunnels has an external diameter of 14 ft. and that for the cast-iron-lined tunnels 13 ft. 1 in. The machine consists essentially of two drums; that for the 14-ft. diameter tunnels has an outer drum of 14 ft. external diameter and 9 ft. long and the leading end is bevelled to form a cutting edge. Within the main drum there is a 7-ft. 6-in. diameter rotating drum, 5 ft. 6 in. long, carried on two roller races and provided with a thrust ring to take the axial load from the rotating cutters. The cutting teeth are mounted on six arms at the front of the shield, each arm having up to eight removable teeth, mounted at the outer edge of the rotating drum, so that they cut the ground in an annular area in front of the space between inner and outer drums.

The ground in front of the inner drum is cut by teeth mounted on a removable arm across the inner drum. The inner drum and cutting teeth are rotated at speeds of up to 4 revs. per minute by six hydraulic motors.

The forward movement of the shield is effected by fourteen hydraulic rams arranged at equal intervals around the periphery of the shield and pushing against the last completed ring of lining. The rams, which have a stroke of 2 ft. 8 in., are controlled separately by an operator standing behind the rotating inner drum within the shield casing. The operator is provided with sighting guides which show whether the shield is on the correct line and level and he can increase or reduce the pressure on any of the rams to correct any tendency of the shield to deviate from the correct alignment. The clay is cut by the teeth, and by means of scoops and paddles it is guided into a hopper within the shield where it drops on to the end of an inclined belt-conveyor, which discharges on to the main horizontal belt-conveyor on which the excavated clay is carried along a staging to be discharged into skips running on a 2-ft. gauge track on each side of the conveyor. The whole of this equipment including the staging is mounted on an articulated trailing platform which is attached to the rear of the shield and is drawn forward as the shield advances. When the rams have pushed the shield forward a distance equal to the width of a ring of lining, that is 2 ft., they are retracted. A ring of lining is then placed in the space between the last completed ring and the rear of the shield. When this has been completed the cycle is repeated, the rams thrusting against the newly-placed ring.

The "drum digger" is capable, in good conditions, of advancing more than 60 ft. in three 8-hour shifts, over long periods. The greatest length of tunnel driven to date in 24 hours is 88 ft.

Concrete Lining.

The precast concrete blocks for the lining are of a new type. The tunnel is bored to provide for a tube of 12 ft. 6 in. internal diameter with a lining of concrete blocks. Blocks of various thicknesses from 4½ in. to 9 in. have been tried. The thickness likely to be used eventually

will be 6 in. Each tunnel ring is made up of fourteen identical blocks each having one cross-joint face convex and the other concave, so that they fit together with knuckle joints. When the fourteen blocks are assembled a gap of about 7 in. remains at the top, and is filled by a pair of reinforced concrete folding wedges having plane contact faces with concave and convex faces respectively in contact with the blocks on each side. The wedge, with the wider end towards the shield, is driven home by a pair of small hydraulic rams while the other wedge is held in position. The two wedges hold the whole ring firmly in place. The wedges are seen in place at the top of Fig. 1.

The blocks have four holes spaced equally around the inner face and into which bolts are fixed for handling the blocks in the tunnel and which will also be used for fixing permanent tunnel equipment. The blocks are handled by hoists at the working face, an expanding bolt placed in one of the holes being used to lift them. They are hoisted into their correct positions by an arm mounted at the rear of the shield, and are held in place by pull-out "needles" until the concrete wedges are driven into position. When firmly in position, the lining bears against the face of the excavation in the clay.

Precast Blocks.

The concrete blocks, which are made at a works at Waltham Abbey, are not reinforced and are of concrete having a crushing strength of not less than 5500 lb. per square inch. The mixing water is at a temperature of 140 deg. F. at the time of gauging. Ordinary Portland cement is used.

The blocks are lifted by crane, the tackle of which is attached to eye-bolts let into holes in the blocks. The convex and concave ends are coated with bituminous paint. At the site, the blocks are secured in a rope-sling, four at a time, and lowered into the shaft and placed on a train of bogies which carries in one journey the fourteen blocks required for one ring.

For the concrete-lined tunnel the consulting engineers are Sir William Halcrow & Partners. The contractors are Messrs. Kinnear Moodie & Co., Ltd. The precast concrete blocks and wedges were made by Messrs. Charles Brand & Son, Ltd.

Slabs for Liquid-containing Structures.

DESIGN IN ACCORDANCE WITH B.S. CODE OF PRACTICE
No. 2007 (1960).

The accompanying tables give data to enable the walls and other slabs in a structure containing water or other aqueous liquid to be designed quickly in accordance with the recommendations of British Standard Code No. 2007 (1960). There are three principal cases to consider, namely, (I) Slabs subjected to bending only; (II) Slabs subjected to direct tension only; and (III) Slabs subjected to bending and direct tension. *Table A* deals with cases I and II and *Table B* with case III. The following conditions are applicable to all cases.

The tensile stress p_{st} in the reinforcement shall not exceed 12,000 lb. per square inch (except in tensile reinforcement near the face remote from the liquid for slabs not less than 9 in. thick).

The nominal volumetric proportions of the concrete shall be 1 : 1.6 : 3.2 and the compressive stress p_{cb} in this concrete shall not exceed 1200 lb. per square inch; this requirement is seldom critical. The tensile stress p_{ct} in concrete of this mixture shall not exceed 190 lb. per square inch in slabs in direct tension and 270 lb. per square inch in slabs in bending; this requirement applies when it is necessary to design for resistance to cracking.

The cover of concrete over the reinforcement shall be not less than $1\frac{1}{2}$ in. or the diameter of the bar if exceeding $1\frac{1}{2}$ in.

The modular ratio m shall be assumed to be 15.

The proportion $r_o \left(= \frac{A_{st}}{bd} \right)$ of reinforcement shall be not less than 0.003 with plain bars and 0.0025 with deformed bars.

Symbols used additional to those in the foregoing are as follows,

d, d_1, b, l_a : Thickness, effective depth, breadth and lever-arm respectively of slab.

M'_{rc}, M'_{rs} : Moment of resistance when not cracked and cracked respectively based on the thickness.

Q : Moment-of-resistance factor without compression reinforcement based on the effective depth.

R_c, R_s : Factors for moment of resistance corresponding to M'_{rc} and M'_{rs} respectively.

Case I.—Slabs Subjected to Bending Only.

Slabs subjected to bending have to be designed to resist cracking and, should cracking occur, they must be reinforced sufficiently and be sufficiently thick to avoid overstressing the reinforcement in tension or the concrete in compression. The basic formulæ, which are derived from the modular-ratio method of determining the resistance, are as follows.

RESISTANCE TO CRACKING.



$$M'_{rc} = R_c d^3 = \frac{p_{ct}}{1 - n_o} \left[\frac{1}{3} - (1 - n_o)n_o + r_o(m - 1) \left(\frac{d_1}{d} - n_o \right)^2 \right] b d^3,$$

$$\frac{1}{2} + r_o \left(\frac{d_1}{d} \right) (m - 1)$$

in which

$$n_o = \frac{\frac{1}{2} + r_o \left(\frac{d_1}{d} \right) (m - 1)}{1 + r_o(m - 1)}.$$

TABLE A.—BENDING ONLY.

IN ACCORDANCE WITH B. S. CODE NO. 2007. CONCRETE: NOMINAL PROPORTIONS 1:1.6:3.2 $m = 15$ MINIMUM PROPORTION OF REINFORCEMENT $r_o = \frac{A_{st}}{bd} \leq 0.003$ MINIMUM COVER: $1\frac{1}{2}$ IN. BENDING MOMENT = M IN.-LB. PER FOOT.																																																						
CASE I A BENDING ONLY (TENSILE STRESS IN CONTACT WITH LIQUID)	<u>RESISTANCE TO CRACKING.</u> DETERMINES THICKNESS d . GIVEN OR ASSUME r_o AND $\frac{d_1}{d}$ $d \leq \sqrt{\frac{M}{R_c}} \left[\text{WHERE } R_c = \frac{3240}{1 - n_o} \left[\frac{1}{3} - (1 - n_o)n_o + 14r_o \left(\frac{d_1}{d} - n_o \right)^2 \right] \right]$ AND $n_o = \frac{\frac{1}{2} + 14r_o \left(\frac{d_1}{d} \right)}{1 + 14r_o}$	$M_{rc}^V = R_c d^2$ $p_{ct} \geq 270 \text{ LB./SQ. IN.}$																																																				
	<u>DESIGN FOR STRENGTH.</u> DETERMINES REINFORCEMENT A_{st} . $A_{st} \leq \frac{M}{12,000 a_1 d_1} \text{ WHERE } a_1 = 1 - \frac{1}{3} n_1$ AND $n_1 = \sqrt{r_s^2 + 2r_s - r_s}; \quad r_s = 15r_o \left(\frac{d}{d_1} \right)$ $[R_s = 144,000 r_o a_1 d_1 d]$	$M_{rs}^V = R_s d^2$ $p_{st} \geq 12,000 \text{ LB./SQ. IN.}$																																																				
	<u>BALANCED DESIGN</u> POINTS THUS \odot INDICATE VALUES OF r_o AND $R_c = R_s = R_E$ FOR BALANCED DESIGN AND ARE APPLIED IN THE TABLE BELOW TO SLABS OF THE THICKNESS STATED.																																																					
		<table><tr><th>d IN.</th><th>d_1 IN.</th><th>$M_{rc}^V = M_{rs}^V$ IN.-LB./FT.</th><th>A_{st} ϕ SQ. IN./FT.</th></tr><tr><td>4</td><td>2.25</td><td>8,800</td><td>$\frac{1}{2}$ 0.33</td></tr><tr><td>4$\frac{1}{2}$</td><td>2.69</td><td>10,300</td><td>0.41</td></tr><tr><td>5</td><td>3.19</td><td>14,200</td><td>0.43</td></tr><tr><td>6</td><td>4.19</td><td>20,800</td><td>$\frac{5}{8}$ 0.49</td></tr><tr><td>7</td><td>5.19</td><td>29,200</td><td>0.54</td></tr><tr><td>8</td><td>6.19</td><td>38,800</td><td>0.60</td></tr><tr><td>9</td><td>7.12</td><td>29,400</td><td>0.66</td></tr><tr><td>10</td><td>8.12</td><td>61,800</td><td>$\frac{3}{4}$ 0.72</td></tr><tr><td>12</td><td>10.12</td><td>91,100</td><td>0.85</td></tr><tr><td>15</td><td>13.06</td><td>144,200</td><td>$\frac{7}{8}$ 1.05</td></tr><tr><td>18</td><td>16.0</td><td>211,200</td><td>1 1.25</td></tr><tr><td>24</td><td>22.0</td><td>380,100</td><td>1$\frac{1}{2}$ 1.64</td></tr></table>	d IN.	d_1 IN.	$M_{rc}^V = M_{rs}^V$ IN.-LB./FT.	A_{st} ϕ SQ. IN./FT.	4	2.25	8,800	$\frac{1}{2}$ 0.33	4 $\frac{1}{2}$	2.69	10,300	0.41	5	3.19	14,200	0.43	6	4.19	20,800	$\frac{5}{8}$ 0.49	7	5.19	29,200	0.54	8	6.19	38,800	0.60	9	7.12	29,400	0.66	10	8.12	61,800	$\frac{3}{4}$ 0.72	12	10.12	91,100	0.85	15	13.06	144,200	$\frac{7}{8}$ 1.05	18	16.0	211,200	1 1.25	24	22.0	380,100	1 $\frac{1}{2}$ 1.64
d IN.	d_1 IN.	$M_{rc}^V = M_{rs}^V$ IN.-LB./FT.	A_{st} ϕ SQ. IN./FT.																																																			
4	2.25	8,800	$\frac{1}{2}$ 0.33																																																			
4 $\frac{1}{2}$	2.69	10,300	0.41																																																			
5	3.19	14,200	0.43																																																			
6	4.19	20,800	$\frac{5}{8}$ 0.49																																																			
7	5.19	29,200	0.54																																																			
8	6.19	38,800	0.60																																																			
9	7.12	29,400	0.66																																																			
10	8.12	61,800	$\frac{3}{4}$ 0.72																																																			
12	10.12	91,100	0.85																																																			
15	13.06	144,200	$\frac{7}{8}$ 1.05																																																			
18	16.0	211,200	1 1.25																																																			
24	22.0	380,100	1 $\frac{1}{2}$ 1.64																																																			
CASE I B BENDING ONLY (TENSILE STRESS AT FACE REMOTE FROM LIQUID)	(a) $d < 9$ IN. ADOPT CASE I A.																																																					
	(b) $d \leq 9$ IN. DESIGN FOR STRENGTH ONLY $p_{st} \geq 18,000 \text{ LB./SQ. IN. (PLAIN BARS) OR } 20,000 \text{ LB./SQ. IN. (DEFORMED BARS)}$ $p_{cb} \geq 1200 \text{ LB./SQ. IN.}$ <u>DESIGN.</u> $d_1 \leq \sqrt{\frac{M}{3000}} \text{ (PLAIN BARS) OR } \sqrt{\frac{M}{2872}} \text{ (DEFORMED BARS)}$ $d = d_1 + 1\frac{1}{2} \text{ IN.} + \frac{1}{2} \text{ (DIAM. OF BAR).}$ $A_{st} = \frac{M}{15,000 d_1} \text{ (PLAIN BARS) OR } \frac{M}{16,840 d_1} \text{ (DEFORMED BARS). } r_o = \frac{A_{st}}{12d}$ <u>STRESSES.</u> GIVEN d , d_1 AND r_o . n_1 AND a_1 AS CASE I A. $f_{st} = \frac{M}{12r_o a_1 d_1 d} \quad f_{cb} = \frac{f_{st} n_1}{15(1 - n_1)}$																																																					

RESISTANCE WHEN CRACKED.

$$M_{rs} = R_s d^3 = p_{st} r_0 \left(1 - \frac{n_1}{3} \right) \left(\frac{d_1}{d} \right) b d^3$$

in which

$$n_1 = \sqrt{\left[m r_0 \left(\frac{d}{d_1} \right) \right]^2 + 2 m r_0 \left(\frac{d}{d_1} \right) - m r_0 \left(\frac{d}{d_1} \right)}.$$

When the permissible tensile stresses in the concrete (p_{ct}) and reinforcement (p_{st}) are 270 lb. and 12,000 lb. per square inch respectively, and $m = 15$, as recommended in the Code, the foregoing expressions are as given in Table A for a strip of slab 12 in. wide ($b = 12$ in.). The curves in the table give values of R_c and R_s for various values of $\frac{d_1}{d}$ and r_0 . It is seen that for each ratio of $\frac{d_1}{d}$ there is a proportion r_{0E} of reinforcement

which gives equal values of R_c and R_s , say R_E ; this is the ideal case, the adoption of which gives the most economical design. If this value of R_E is substituted in

$d = \sqrt{\frac{M}{R_E}}$, in which M is the bending moment to be resisted, the resulting value of d is the thickness of slab which complies with the two design requirements if the area of reinforcement A_{st} in a strip 1 ft. wide is not less than $12 r_{0E} d^2$ sq. in.; corresponding values of r_{0E} and R_E are given in Table A.

Conversely, the resistances of slabs of various thicknesses with the proportion of reinforcement indicated by r_{0E} can be obtained by substitution in $M_r = R_E d^3$; the resistances and reinforcement of slabs of various thicknesses taking into account the probable value of $\frac{d_1}{d}$ are also given in Table A.

SLABS NOT LESS THAN 9 IN. THICK.—The foregoing basis of design applies to all slabs when the strain at the face in contact with the liquid is tensile, and to slabs less than 9 in. thick whether tensile strain occurs at the face in contact with, or remote from, the liquid. If in a slab not less than 9 in. thick, the tensile strain is at the face remote from the liquid, the method of design is as for an ordinary slab with the stress in the reinforcement not greater than 18,000 lb. per square inch in plain bars or 20,000 lb. per square inch in deformed bars, and the compressive stress in the concrete not greater than 1200 lb. per square inch. For these conditions, which apply to case IA in Table A, the effective depth d_1 of the slab must be not less than

$\sqrt{\frac{M}{Qb}}$ in which Q is the moment-of-resistance factor and is 250 for $p_{st} = 18,000$ lb., and 239 for $p_{st} = 20,000$ lb. per square inch. The thickness of the slab must be not less than $[d_1 + 1\frac{1}{2}$ in. (cover) + $\frac{1}{2}$ (diameter of bar)].

If the thickness of the slab provided is such that the effective depth is equal to the value calculated from $\sqrt{\frac{M}{Qb}}$, the values of A_{st} are $0.017 b d_1$, and $0.014 b d_1$ sq. in. in width b if p_{st} is 18,000 lb. and 20,000 lb. respectively. It is, however, uncommon for the effective depth to be equal exactly to the minimum depth required, and is generally greater; in this case the area A_{st} of the reinforcement in square inches in width b is given by $\frac{M}{p_{st} l_a}$ in which $l_a = 0.83 d_1$ approximately in all cases.

Conversely, the moment of resistance of a slab is given by $Q b d_1^2$ if the amount of reinforcement is not less than $0.017 b d_1$ (or $0.014 b d_1$ with deformed bars); the moments of resistance and corresponding amounts of reinforcement in slabs of various thicknesses are given in Table A for probable values of $\frac{d_1}{d}$.

Examples.—Bending Only (Table A).

Design walls of tanks for the conditions stated (Case IA).

(a).—Bending moment of 20,000 in.-lb. per foot.

This design can be taken directly from the table headed "Balanced Design", since the moment of resistance of a 6-in. slab is approximately 20,000 in.-lb. The reinforcement required is (also from the table) 0.49 sq. in. per foot, which is provided by $\frac{3}{4}$ -in. bars at 7 $\frac{1}{2}$ -in. centres with 1 $\frac{1}{2}$ -in. cover.

(b).—Bending moment of 24,000 in.-lb. per foot.

The curves on the table can be used directly to obtain a "balanced design." Assume $\frac{d_1}{d} = 0.7$. (Compare with values on table headed "Balanced Design".) From curves,

$R_e = R_s = R_E = 580$ and $r_0 = 0.0067$. $d = \sqrt{\frac{24,000}{580}} = 6.45$ in.; that is, a 6 $\frac{1}{2}$ -in. slab is required. $A_{st} = 0.0067 \times 6\frac{1}{2} \times 12 = 0.522$ sq. in.; provide $\frac{3}{4}$ -in. bars at 7-in. centres with 1 $\frac{1}{2}$ -in. cover.

(c).—Check that an 8-in. slab reinforced with $\frac{3}{4}$ -in. bars at 6-in. centres with 1 $\frac{1}{2}$ -in. covers and subjected to a bending moment of 36,000 in.-lb. per foot conforms to B.S. Code No. 2007.

$$d_1 = 8 - 1\frac{1}{2} - \frac{3}{4} = 6.19 \text{ in.}; \frac{d_1}{d} = \frac{6.19}{8} = 0.774; \frac{d}{d_1} = \frac{1}{0.774} = 1.29. \quad A_{st} = 0.614 \text{ sq. in.};$$

$$r_0 = \frac{0.614}{12 \times 8} = 0.0064. \quad \text{Substitute in formulæ in Table A.}$$

$$n_0 = \frac{\frac{1}{2} + (14 \times 0.0064 \times 0.774)}{1 + (14 \times 0.0064)} = 0.523.$$

$$R_e = \frac{3240}{1 - 0.523} \left\{ \frac{1}{2} - (1 - 0.523) 0.523 + [14 \times 0.0064 (0.774 - 0.523)^2] \right\} = 607.$$

$$d \leq \sqrt{\frac{36,000}{607}} = 7.70 \text{ in., which does not exceed 8 in.}$$

$$r_s = 15 \times 0.0064 \times 1.29 = 0.124; n_1 = \sqrt{(0.124)^2 + (2 \times 0.124)} = 0.124 = 0.39.$$

$$a_1 = 1 - (\frac{1}{2} \times 0.39) = 0.87; A_{st} \leq \frac{36,000}{12,000 \times 0.87 \times 6.19} = 0.558 \text{ sq. in. per foot.}$$

which does not exceed 0.614 sq. in. Therefore design is satisfactory.

Note.—For designs in Case IB, the procedure is as in the foregoing if $d < 9$ in., and as for ordinary designs if $d \leq 9$ in.

Case II.—Slabs Subjected to Direct Tension Only.

Planar slabs subjected to direct tension only without bending are not common; a curved slab, such as the wall of a cylindrical tank, is the more common case. The two conditions of design are that the tensile stress p_{et} in the concrete should not be so great as to cause cracking, and, should cracking occur, the reinforcement should be able to resist the whole of the tensile force T without exceeding the permissible stress p_{st} . The first of these conditions determines the thickness of the slab such that

$$T = p_{et}[db + (m - 1)A_{st}].$$

The second condition determines the amount of reinforcement, such that $T = p_{st}A_{st}$. For the most effective design, therefore, if $A_{st} = r_0 bd$, equating the two expressions for T gives

$$r_0 = \frac{1}{\frac{p_{st}}{p_{et}} - (m - 1)} \quad \text{and} \quad d = \frac{T}{[1 + (m - 1)r_0]b p_{et}}.$$

The expressions for Case II in Table B give values of r_0 and d for a slab 12 in. wide subjected to a tensile force T lb. per foot, if the permissible stresses p_{et} and p_{st} are 190 lb. and 12,000 lb. per square inch respectively as recommended in the Code for 1 : 1.6 : 3.2 concrete and any type of reinforcement; $m = 15$.

Case III.—Slabs Subjected to Direct Tension Combined with Bending.

The two cases are A when the tensile strain is at the face in contact with the liquid, and B when this face is subjected to compressive strain and the opposite face to tensile strain.

CASE IIIA. TENSILE STRAIN AT FACE IN CONTACT WITH LIQUID.—There are two conditions for this case, namely, when tensile stresses only are produced, and when tensile and compressive stresses are produced. If the direct tension is T and the bending moment is M , $e = \frac{M}{T}$.

(a) *Tensile Stresses Only.*—This condition, which occurs when e does not exceed $d_1 - \frac{1}{2}d$, is analogous to a slab subjected to direct tension only and therefore the tensile stress in the concrete must not exceed the stress p_{ct} permissible in direct tension if no cracking is to occur. Should cracking occur, the permissible tensile stress p_{st} in the reinforcement must not be exceeded. The latter condition determines the amount of reinforcement and if there is the same amount of reinforcement near each face, the proportion r_0 of reinforcement near each face must be not less than given by

$$r_0 = \frac{T}{2p_{st}bd} \left[1 + \frac{e}{d_1 - \frac{1}{2}d} \right].$$

The permissible tensile stress in the concrete is not exceeded if

$$\frac{T}{bd} \left[\frac{1}{1 + 2r_0(m-1)} + \frac{e}{\left[\frac{1}{6} + 4r_0(m-1) \left(\frac{d_1}{d} - \frac{1}{2} \right)^2 \right] d} \right] \leq p_{ct}.$$

The thickness of the slab is determined from this requirement.

Evaluation of these expressions for $p_{ct} = 190$ lb. per square inch, $p_{st} = 12,000$ lb. per square inch, $b = 12$ in., and $m = 15$, are given in Table B.

(b) *Tensile and Compressive Stresses.*—This condition, which occurs when e exceeds $d_1 - \frac{1}{2}d$, is analogous to a slab subjected to bending only, and therefore the limiting stresses for that condition apply. Since the effect of reinforcement in the compression zone of a slab is insignificant, such reinforcement, if any, can be neglected. Given dimensions d and d_1 , the proportion r_0 of tensile reinforcement required to ensure that the steel is not overstressed should cracking occur is given by

$$r_0 = \frac{T}{p_{st}bd} \left(1 + \frac{e + \frac{1}{2}d - d_1}{l_a} \right).$$

The position of the neutral plane if cracking does not occur is given by

$$n_0 = \frac{\frac{1}{2} + (m-1) \left(\frac{d_1}{d} \right) r_0}{1 + (m-1)r_0}.$$

To ensure cracking does not occur, the slab must be thick enough, and this is so if

$$\frac{T}{bd} \left[\frac{1}{1 + (m-1)r_0} + \frac{e(1-n_0)}{d \left[\frac{1}{3} - (1-n_0)n_0 + r_0(m-1) \left(\frac{d_1}{d} - n_0 \right)^2 \right]} \right] \leq p_{ct}.$$

The corresponding expressions in Table B are for the condition $p_{ct} = 270$ lb. per square inch, $p_{st} = 12,000$ lb. per square inch, $b = 12$ in., and $m = 15$.

TABLE B.—DIRECT FORCE WITH OR WITHOUT BENDING.

IN ACCORDANCE WITH B. S. CODE No. 2007. CONCRETE: NOMINAL PROPORTIONS 1:1.6:3-2 MINIMUM PROPORTION OF REINFORCEMENT: $r_o = \frac{A_{st}}{bd} \leq 0.003$. MINIMUM COVER: $1\frac{1}{2}$ IN. DIRECT TENSILE FORCE = T.L.B. PER FOOT. BENDING MOMENT = MIN. LB. PER FT.		$m = 15$
CASE II	DESIGN FOR STRENGTH. DETERMINES REINFORCEMENT A_{st} . $P_{ct} \geq 12,000 \text{ LB./SQ. IN.}$ $A_{st} = \frac{T}{12,000} \text{ SQ. IN./FT. OR } r_o = \frac{T}{144,000d}$ RESISTANCE TO CRACKING DETERMINES THICKNESS d : $P_{ct} \geq 190 \text{ LB./SQ. IN.}$ $A_{st} = 12r_o d$ $d \leq \left[\frac{T}{2280} - 1.17 A_{st} \right] \text{ IN.}$ [IF MORE THAN ONE ROW OF BARS:— A_{st} = TOTAL OF ALL ROWS.] BALANCED DESIGN. $d = \frac{T}{2930} \text{ IN.}$ $A_{st} = 0.244d \text{ SQ. IN./FT.}$	
CASE IIIA	(a) $e \geq (d_1 - \frac{1}{2}d)$. TENSILE STRESSES ONLY. $P_{ct} \geq 190 \text{ LB./SQ. IN.}$ GIVEN OR ASSUME d AND d_1 $P_{st} \geq 12,000$ DETERMINE $r_o' = \frac{T}{288,000d} \left[1 + \frac{e}{d_1 - \frac{1}{2}d} \right]$ [PROVIDE A_{st} AT BOTH SIDES] $A_{st}' = 12r_o'd$ SUBSTITUTE IN $f_{ct} = \frac{T}{12d} \left[\frac{1}{1 + 28r_o'} + \frac{cd}{\frac{1}{6}d^2 + 56r_o'(d_1 - \frac{1}{2}d)^2} \right] \geq 190$ ADJUST d UNTIL EXPRESSION IS SATISFIED. $A_{st}' = 12r_o'd$	
CASE IIIA	(b) $e > (d_1 - \frac{1}{2}d)$. TENSILE AND COMPRESSIVE STRESSES. $P_{ct} \geq 270 \text{ LB./SQ. IN.}$ GIVEN OR ASSUME d AND d_1 $P_{st} \geq 12,000$ DETERMINE $r_o = \frac{T}{144,000d} \left[1 + \frac{e + \frac{1}{2}d - d_1}{0.83d_1} \right]$ $A_{st} = 12r_o d$ $n_o = \frac{\frac{1}{2} + 14r_o \frac{d_1}{d}}{1 + 14r_o}$ [NEGLECT COMPRESSION REINFORCEMENT.] SUBSTITUTE IN $\frac{T}{12d} \left\{ \frac{1}{1 + 14r_o} + \frac{e(1 - n_o)}{[\frac{1}{3} - (1 - n_o)n_o + 14r_o(\frac{d_1}{d} - n_o)^2]} d \right\} \geq 270$ ADJUST d UNTIL EXPRESSION IS SATISFIED.	
CASE IIIB	(a) $d < 9 \text{ IN.}$ ADOPT CASE IIIA. (b) $d \leq 9 \text{ IN.}$ $P_{st} = 18,000 \text{ LB./SQ. IN. (20,000 LB./SQ. IN. FOR DEFORMED BARS)}$ $P_{cb} \geq 1200 \text{ LB./SQ. IN. - NOT CRITICAL.}$ DIAGRAM AS CASE IIIA (b) GIVEN OR ASSUME d AND d_1 $\left[d_1 \leq \sqrt{\frac{M}{3000}} \text{ (PLAIN BARS)} \text{ OR } \sqrt{\frac{M}{2072}} \text{ (DEFORMED BARS)} \right]$ $e_s = e + \frac{1}{2}d - d_1$ $A_{st} = \frac{T}{18,000 \text{ OR } 20,000} \left[1 + \frac{e_s}{0.83d_1} \right] \text{ SQ. IN./FT.}$ IF d , d_1 AND A_{st} GIVEN:— $f_{st} = \frac{T}{A_{st}} \left[1 + \frac{e_s}{0.83d_1} \right] \geq 18,000 \text{ (OR } 20,000)$	

CASE IIIB. TENSILE STRAIN AT FACE REMOTE FROM LIQUID.—Two conditions are to be considered, namely, when the slab is less than and not less than 9 in. thick.

(a) *Slab less than 9 in. thick.*—For this case the design should be exactly as for Case IIIA, applying sub-case (a) or (b) as applicable.

(b) *Slab not less than 9 in. thick.*—If d and d_1 are known, or assumed, the area of tensile reinforcement required is calculated from

$$A_{st} = \frac{T}{p_{st}} \left(1 + \frac{e_s}{l_a} \right)$$

in which $e_s = e + \frac{1}{2}d - d_1$.

An approximate value for d_1 (from which d can be determined) is $\sqrt{\frac{M}{Qb}}$ in which Q is the moment of resistance factor corresponding to the permissible stresses p_{st} and p_{cb} in the steel and concrete respectively. If M is large in respect to T , that is, if e is large, say greater than d_1 , the value of d_1 required to ensure that p_{cb} is not exceeded should differ much from the value calculated from the foregoing expression; if e is smaller than d_1 a slightly thinner slab may be sufficient. In doubtful cases, the maximum compressive stress should be calculated by one of the ordinary methods of combined stress.

The expressions in subsection (b) of Case IIIB in Table B apply to the conditions $p_{st} = 18,000$ lb. for plain bars or 20,000 lb. per square inch for deformed bars, p_{cb} not exceeding 1200 lb. per square inch, $b = 12$ in., and $m = 15$.

Examples.—Tension with and without Bending (Table B).

Design walls of tanks for the conditions stated.

(a).—Direct tensile force of 25,000 lb. per foot (no bending).—Case II.

$$(i) \quad d = \frac{25,000}{2930} = 8.53 \text{ in.; say } 8\frac{1}{2}\text{-in. slab.}$$

$A_{st} = 0.244 \times 8.5 = 2.07$ sq. in. per foot; provide 1-in. bars at 9-in. centres in each of two rows.

(ii) Alternative method. $A_{st} = \frac{25,000}{12,000} = 2.08$ sq. in. per foot; provide 1-in. bars at 9-in. centres (total = 2.09 sq. in.) in each of two rows.

$$d < \left[\frac{25,000}{2280} - (1.17 \times 2.09) \right] = 8.53 \text{ in.; that is, } 8\frac{1}{2}\text{-in. slab.}$$

(b). Tensile force of 12,000 lb. per foot, and bending moment of 20,000 in.-lb. per foot. Assume $d = 8$ in. and $d_1 = 8 - 2 = 6$ in.; $d_1 - \frac{1}{2}d = 6 - 4 = 2$ in.

$$e = \frac{20,000}{12,000} = 1.67 \text{ in. } (> 2 \text{ in.; therefore Case IIIA } a \text{ applies.})$$

$$r_{st} = \frac{12,000}{288,000 \times 8} \left(1 + \frac{1.67}{2} \right) = 0.0095.$$

$$f_{ct} = \frac{12,000}{12 \times 8} \left[\frac{1}{1 + (28 \times 0.0095)} + \frac{1.67 \times 8}{(\frac{1}{2} \times 8^2) + (56 \times 0.0095 \times 2^2)} \right]$$

= 230 lb. per square inch (approx.) which exceeds 190 lb. per square inch.

Recalculate with $d = 9$ in., and $d_1 = 7$ in.; $d_1 - \frac{1}{2}d = 2\frac{1}{2}$ in.

$r_{st} = 0.0077$; $f_{ct} = 195$ lb. per square inch (≈ 190); satisfactory if A_{st} is slightly greater than $12 \times 0.0077 \times 9 = 0.83$ sq. in. per foot; provide say 1-in. bars at 10 $\frac{1}{4}$ -in. centres at each face (total = 0.898 sq. in. per foot).

(c).—Tensile force of 10,000 lb. per foot and bending moment of 48,000 in.-lb. per foot.

Assume $d = 10$ in. and $d_1 = 8$ in.; $\frac{d_1}{d} = 0.8$; $e = \frac{48,000}{10,000} = 4.8$ in. ($> 8 - 5 = 3$ in.; therefore Case IIIA *b* applies.)

$$r_s = \frac{10,000}{144,000 \times 10} \left(1 + \frac{4.8 + 5 - 8}{0.83 \times 8} \right) = 0.0088; \quad 14r_s = 0.122.$$

$$n_s = \frac{0.5 + (0.122 \times 0.8)}{1.122} = 0.532.$$

$$f_{et} = \frac{10,000}{12 \times 10} \left\{ \frac{1}{1.122} + \frac{4.8(1 - 0.532)}{(1 - (1 - 0.532)0.532 + 0.122(0.8 - 0.532)^2)10} \right\}$$

= 275 lb. per square inch (≈ 270); satisfactory if A_{et} is slightly greater than $12 \times 0.0088 \times 10 = 1.06$ sq. in. per foot; provide 1-in. bars at 8-in. centres (1.178 sq. in.) at tensile face.

Note.—For designs in Case IIIB, the procedure is as in the foregoing if $d < 9$ in., and as for ordinary designs if $d \leq 9$ in.

Gap-graded Aggregate in Concrete for Marine Works.

WHAT is probably the first instance in this country of gap-graded aggregate being used in concrete for marine works is in the reconstruction of the sea-wall at Dymchurch, Kent. The wall, which is to be improved and strengthened, is along a very exposed coast-line, and is nearly a mile in length, extending between the Grand Redoubt and Willop Sluice. Separate tenders were invited for reconstruction of the wall in granite, or in ordinary dense concrete, or in any other form of construction proposed by the contractors tendering. The cost of construction in granite was excessive. The tender accepted is for precast concrete blocks and cast-in-situ concrete using gap-graded aggregate. In preliminary tests the resistances to abrasion, frost and absorption of this type of concrete were examined. The results indicate that concrete of suitable mixture with gap-graded aggregate might well prove superior to concrete with continuously-graded aggregate especially as regards resistance to abrasion.

The profile of the existing apron is to be re-formed by means of plain concrete filling and the sea-wall is to be extended about 19 ft. seawards to a new row of timber sheet-piles. The wider apron, the increased total width of which will be about 80 ft., will have the effect of reducing the action of waves on the wall. The precast blocks, which will be made in a casting yard established on the site, will form the surface of the new apron. Towards the upper part of the apron a concrete berm 20 ft. wide will be con-

structed. On the top of the wall a roadway 15 ft. wide will be constructed with a parapet on the landward-side as a protection against waves washing over and scouring out the ground behind the wall. Various ramps and steps will also be constructed.

There is no record of the time when the first clay sea-wall was built at Dymchurch but it is known to have undergone several alterations during its lifetime. In recent years it became apparent that repairs were needed along the section of the sea-defence works where reconstruction is now to be carried out. Abrasion has worn away much of the stone facing of the old apron, and from time to time damage by storms to the middle section has necessitated costly repairs. The large quantities of water carried over by onshore gales have on occasions scoured out parts of the back of the wall. To reduce the risk of further damage, the action of waves on the wall will be mitigated by creating shallower water at the middle of the apron and by laying heavy concrete blocks.

The work is being carried out for the Kent River Board under the direction of the Chief Engineer, Mr. J. I. Taylor, M.B.E., M.I.C.E. The probable cost is £430,000 and the contract time is three years, but it is hoped that the work will be completed in less time. The contractors are Messrs. Holland & Hannen and Cubitts (Great Britain) Ltd. The consulting engineers for the development of the gap-graded concrete are Messrs. Sandberg.

The £.s.d of OSAL*
— Surface waterproofing of
Brick, Concrete and Stone.

**It's not the cost
per gallon
but
the cost per yard
that counts**

Using Neocosal, a 1½d. per square foot is all that it costs effectively to provide surface waterproofing of Brick, Concrete and Stone. Neocosal, a colourless liquid water repellent, penetrates the surface, forming an effective water seal.



Leading Architects have been specifying Neocosal for 30 years or more, for its economy, efficiency and because it does not discolour surfaces. Send for information Leaflet No. 3.

** Osal is the generic name for the products of A. A. BYRD & CO. LTD.—Florosal, Neocosal, Tricosal and Lubrosal. Literature about each individual product is available on request.*

A. A. BYRD & CO. LTD. (Dept CB) 210 TERMINAL HOUSE, GROSVENOR GARDENS, LONDON, S.W.1
Phone: StOsane 5236 Grams: Byrdleom, Wesphone, London Works: Basingstoke, Hants



BOC PROPANE MEANS POWER MORE WAYS!

Space-heating! Floodlighting! Defrosting aggregate! Melting mastic for roofing! Four ways in which BOC Propane proves itself the most resourceful fuel on the building site today! More and more applications are being discovered. BOC PROPANE IS VERSATILE. Highly efficient and economical. Clean, low in moisture and sulphur content. British Oxygen pioneered the industrial development of Propane. They have the experience and the resources. Their experts advise how to use BOC Propane efficiently. SUPPLY a complete range of cylinders and equipment. DELIVER promptly anywhere in Britain. BOC PROPANE.

WAYS OF USING BOC PROPANE IN BUILDING

Space-heating • Vehicle fuel
Floodlighting • Heating, cooking, lighting
in builders' huts • Cable jointing
Melting mastic for roofing

SOME BOC PROPANE USERS

Matthew Hall & Co. Ltd.
Mitchell Engineering Ltd.
George Wimpey & Co. Limited.
Woodall-Duckham Construction Company Ltd.

BRITISH OXYGEN ARE PROPANE EXPERTS



THE BRITISH OXYGEN COMPANY LIMITED.

Light Industrial Department, Spencer House, 27 St. James's Place, London, S.W.1 Tel: Hyde Park 7080



A Newspaper Office in London.

THE new office and printing press building (Fig. 1) for the "Daily Mirror" has a maximum height of 169 ft. above the street and is of reinforced concrete construction throughout. In the main building there are twelve storeys above ground, with mezzanine floors in the ground floor and top storeys, and four basement floors

Basements.

Work was begun on the site in 1956. Excavation for the basement retaining walls was carried out in trenches 15 ft. wide struttled from a central dumping of earth. Excavation extended to 45 ft. below the street level for the lowest basement floor, and to over 60 ft. for the lift-



Fig. 1.

where the printing presses, paper stock, and foundry are located. The basement covers the entire area of the site, and the ground and first floors cover most of this area. Above the third floor a tower block covers only part of the site. The primary factor in the design of the building was the installation of the printing presses, each of which weighs about 820 tons. Two presses are already installed, but eventually there will be five, which will cover a floor area of 24,000 sq. ft. The building is shown in the course of construction in Fig. 2.

shafts. This method of construction permitted the central area of the site to be used for the storage of plant and materials while excavation for the retaining walls proceeded around the perimeter of the site.

The retaining walls are designed to span vertically between the base of the wall and the ground floor, and to withstand horizontal pressure of 30 lb. per square foot per foot of depth. The calculated pressure on the ground at the base of the wall is about 3 tons per square foot. The

subsoil over the entire site is London blue clay. The trench was excavated by hand with pneumatic clay-spades. The walls were built in 4-ft. lifts. The vertical face of the clay was lined with precast concrete planks 3 in. thick and 4 ft. in length. The planks were then covered with asphalt

and the concrete for the walls was cast against them. For lengths of 15 ft. on the centre-lines of the columns, the walls are 8 ft. thick, and 5 ft. 6 in. thick for the intervening lengths of 30 ft. On the south side, the wall is 5 ft. thick with an additional 2 ft. of plain concrete to carry




Fig. 2.

for the design and supply of **PRESTRESSING BEDS** and **EQUIPMENT**

you-too-can rely on

One of a batch of
Stelmo prestressing beds
supplied to Richard Costain Ltd.




who offer a unique service in providing
the most economical layout for your
works or on the site for the produc-
tion of pre-tensioned concrete. It
includes the design and supply
of prestressing beds, supports,
wire-handling equipment,
jacks, anchorages, etc.—
all specially designed to
suit your conditions.

STELMO

*the most comprehensive
mould service in the world*

STELMO LTD · WESTWELL LEACON · CHARING · ASHFORD · KENT. Tel: Charing 395-7

You get the lowest relaxation using **SOMERSET** **STABILIZED** Prestressing Wire



COMPARATIVE RELAXATION GRAPH Initial Stress 80 tons/sq. in.
(Drawn wire in the stress relieved and stabilized condition)

- ★ Somerset Wire complies with B.S. 2691
- ★ Is available in plain, indented or helically crimped forms
- ★ Has stable elastic characteristics

STABILIZED by a patented 'Somerset' process

SOMERSET WIRE COMPANY LIMITED



Pengam Moors, Cardiff (Cardiff 37485)

Bridgwater, Somerset (Bridgwater 3001)




Fig. 3.

the foundations of adjacent existing buildings.

The twenty main columns (Fig. 3) in the basements are at 45-ft. centres in both directions and are arranged in five rows of four columns each. At first an excavation 15 ft. square was made for each column base, which in its initial state was sufficient to support the weight of the construction up to and including the second floor. The greatest load on one of the main columns in the completed building is about 3000 tons. The columns are 4 ft. 6 in. in diameter at the bottom and are reinforced with 112 1½-in. bars and 1-in. diameter helical binding at 3-in. centres.

The main columns have projecting corbels (Fig. 3) supporting the three intermediate basement floors, which are flat slabs carried on secondary concrete columns 12 in. square. The upper basement floor is hung from the ground-floor beams by hangers at 15-ft. centres, so that the second basement is completely free of intermediate columns as it is required for the storage of reels of newsprint. Because of the restricted site, vehicles bringing aggregate and other materials and those removing the excavated spoil had to travel over the ground floor, but since the ground floor is designed to carry an internal roadway and the floor of the first basement, it

was sufficiently strong to carry this temporary vehicular load.

After the first 80-ft. length of the ground floor from the northern frontage was completed, which amount was calculated to be sufficient to withstand the horizontal thrust from the top of the retaining wall, the excavation of the dumping, containing 55,000 cu. yd. of clay, was commenced to enable the construction of the basement raft foundation.

The raft was combined with the column bases so that the entire final load on the columns is distributed more or less uniformly over the entire area of the base-

2-ft. ribs with a 4-ft. gap between them. This arrangement allows vertical ducts and services to run uninterruptedly throughout the height of the building. Secondary beams at 15-ft. centres are provided resulting in a grid of beams at 15-ft. centres in two directions.

In the tower, above the third floor, the beams are at 15-ft. centres in a north-south direction only. The columns remain at 45-ft. centres but are rectangular in cross-section except at the northern and southern extremities. Three arched frames (Fig. 4) of 45-ft. span are provided at the third floor to carry the columns



Fig. 4.

ment. The final pressure on the ground under the raft is about 2 tons per square foot which is equivalent to the weight of the material excavated. The whole raft, in addition to being made watertight by a layer of asphalt, overlies porous concrete containing agricultural land-drains connected to stand-pipes embedded in the retaining walls, by which means any water pressure under the raft is relieved. Concreting began with the construction of that part of the raft adjacent to and underpinning the primary column bases and then spread out to the remaining areas.

Superstructure.

The main beams of the first and second floors are 4 ft. wide and span between the main columns, but on the central row of columns the beams are divided into two

supporting the floors in the tower. The beams at the foot of each arch include additional reinforcement to resist a direct tension of 500 tons induced by the arches; therefore each beam 2 ft. wide contains fifty-six 1½-in. bars.

Holes 4½ in. or 9 in. in diameter are formed at 3-ft. centres in the ribs of all beams to enable pipes and other services to pass through without the need for cranking under the beams.

The heating, ventilating and compressed-air plant and the lift-motor rooms are in the top storey of the tower. The height of this storey is 30 ft., this height being required for the lift-motor rooms. An intermediate floor is provided to accommodate the plant and is suspended from the roof beams, thereby reducing the load on the eleventh floor. The walls

When you said: I wouldn't touch additives!
You couldn't have known about
POZZOLITH



Pozzolith—with unique facilities like this mobile laboratory—is more than an additive. It is a means to quality control.

Additives have contributed to the building of many magnificent concrete structures, but only too often they are not intelligently applied and do not give the intended results.

So that you might see the role of additives in true perspective, Pozzolith—the world's leading water reducing admixture, invented as far back as 1932—has recently been introduced to this country. You

now have the opportunity to see and appreciate the values of this concrete control; demonstrated and explained by men who know what concrete will and will not do. Behind them is a research unit unmatched in this field. And on every project on which the Pozzolith method is used, engineers will be on hand to provide unique, on-the-spot, technical assistance.

Write for further details to

Manufactured and distributed in Great Britain by
MILLARS' MACHINERY COMPANY LIMITED,
Pinners Hall, Groat
Winchester Street,
London, E.C.3.
Tel. London Wall 4288

POZZOLITH

Millars

Under licence from THE
MASTER BUILDERS' CO.
A division of American
Marietta Company.



eleven o'clock...

... and

FONDU

CONCRETE

placed yesterday

is ready

for anything

Eleven o'clock—time for the traditional break and reminder that the FONDU concrete laid yesterday morning has reached full strength. Unapproachable speed of maturing is only one of the advantages of FONDU concrete. It also has the unique merit that the concrete is permanent under conditions which destroy ordinary concrete. Many industrial chemicals do not harm Fondu concrete, so that it is the safe solution to much constructional and

repair work in many industries. Also, using firebrick aggregate, CIMENT FONDU provides an adaptable refractory concrete for temperatures up to 1350° C. CIMENT FONDU can save you time and money on your contract work by eliminating waiting time and keeping the concrete section always one step ahead of the others.

Let us send you our 32-page Booklet "THE CEMENT FOR INDUSTRY".

The Cement for Industry

FOR SPEED · STRENGTH ·
RESISTANCE · REFRACTORINESS

LAFARGE ALUMINOUS CEMENT CO. LTD.

73 Brook Street, London, W.1.
Telephone: MAYfair 8546



of the room housing the plant are of light-weight insulating concrete blocks 3 in. thick. The reinforced concrete slab of the eleventh floor is 5 in. thick; on this there is a floating floor comprising a concrete slab, about 4 in. thick, carried on 1½-in. by 1½-in. cork strips forming squares 10 in. by 10 in. The gap between the squares is filled with cork granules and this insulating layer is covered with ½ in. of corrugated paper and roofing felt.

The lifts are at the north and south of the building. The concrete walls of the lift-shafts were constructed independently of the structural floors and were subsequently tied to the floors by means of bars projecting from the floors. Similarly, bars were left projecting to connect to the stairs constructed subsequently.

Loadings.

The floors in the tower are designed for the ordinary imposed office loading of 60 lb. per square foot. At the northern and southern ends of the floors in the tower, the circular columns are retained by beams 4 ft. wide spanning between them and acting as wind bracing; they are designed to withstand the wind pressure on the flank walls of the tower.

The production floors and the main editorial floor are designed for an imposed load of 200 lb. per square foot. The ground floor is designed for an imposed load of 500 lb. per square foot.

To obtain a sufficient pressure, water is stored at two levels. On the eleventh floor, two reinforced concrete tanks having a combined capacity of 34,500 gallons are provided to supply all the floors in the tower block. On the third floor, five reinforced concrete tanks having a total capacity of 34,000 gallons supply all the floors below this level, and are suspended from the arches shown in *Fig. 4*.

External Finishes.

The walls of the ground-floor storey are faced with riven Westmorland dark green slate slabs, which provide a rough-textured base to the building. The northern flank walls are faced with white marble. The northern and southern end walls of the tower are faced with artificial stone with Derbyshire-spar aggregate.

The joint architects and engineers are Sir Owen Williams & Partners and Messrs. Anderson, Forster & Wilcox. The contractors were Messrs. W. & C. French Ltd.

Engineers: Qualifications and Earnings.

THE following has been received from The Engineers' Guild.

"Your very interesting editorial in the April number discusses the booklet entitled 'Professional Engineers' in the 'Choice of Career' series and also the results of the recent survey of engineers' salaries conducted by the Engineers' Guild. The former, as you point out, states that much of the reward of following the profession is the satisfaction to be obtained from mastering problems and from hard and creative work and your apt comment on this is 'It is well that an engineer may have these satisfactions because material rewards may not be so generous.'


The Guild's survey of salaries shows that the remuneration of professional engineers has considerably increased over the last five years but there is, at present, no evidence that their position relative to

other comparable employments has improved. Something more would appear to be required at this stage to attract sufficient numbers of young men to the profession. In the absence of a still better financial return for their work, the extra inducement might be provided by greater prestige and higher status or preferably by both together. You did not deal with this latter aspect, but the Engineers' Guild thinks it very important. Many men (amongst whom may be numbered cabinet ministers) who could obtain better salaries elsewhere, take posts offering less financial remuneration because of the status, prestige and satisfaction attached to such posts. By the use of similar incentives, more engineers would be attracted to the profession and this in turn would provide the enhancement to their status and prestige so long overdue."

FIFTY YEARS AGO.

From "CONCRETE AND CONSTRUCTIONAL ENGINEERING", June, 1911.

Concrete Construction in the Panama Canal.



"The plant used for placing concrete in the two flights of locks on the Pacific slope consists primarily of eight cantilever cranes (as illustrated) of two types, designated respectively, berm and chamber cranes. The berm cranes are equipped with double fixed cantilevers, 150 ft. long, and are 62 ft. 6 in. high to the bottom of the cantilever, and 90 ft. high to the top of the machinery house. The towers are supported by two box girders, each carried on 16 axles. There are two trolleys to each crane, each carrying a 2½ cu. yd. bucket clamshell, which supplies sand and crushed rock from the storage piles beneath the outer ends of the cantilever arms. Each trolley has a rated capacity per hour of 50 cu. yd. of sand and 100 cu. yd. of crushed rock. In each tower are four bins—two for sand and two for crushed rock, each of 15 cu. yd. capacity. Beneath the bins is a platform, where the bags of cement are opened and emptied into hoppers. The cement is transferred to the platform at the rate of 800 bags an hour. The measuring hoppers, which supply the concrete mixers, are placed directly below the cement platform. Each contains three compartments—for sand, crushed rock, and cement respectively. In the tower bases are two concrete mixers, each of 2 cu. yd. capacity, which discharge into 2 cu. yd. buckets carried on flat cars. The operators on the mixer platforms control the discharges by means of compressed air, and also work the chute doors which admit the raw material into the mixers from the measuring hoppers. Water is fed into the mixers from automatic measuring tanks installed in the towers; an instrument records the time consumed in each mixing operation.

The chamber cranes were mainly designed to place the concrete in the lock walls; but are also used in transferring the wood and steel forms from one point to another. Each crane is 97 ft. 6 in. high to the bottom of the cantilever, and 115 ft. high to the top of the machinery house. There are two cantilever arms to each tower—one extended towards the centre wall with a length of 53 ft. 6 in., and the other, 81 ft. 6 in. long, passing over the side wall. The buckets handled by these cranes are of the double-leaf drop-bottom type, and have a capacity of 2 cu. yd. each. The cranes pick up the buckets, deliver them to the lock wall, dump their contents, and deliver the empties to the cars at an average rate of 320 cu. yd. of concrete an hour.

At points in the centre and side walls thermometers were embedded as the concrete reached the successive heights. A complete graphical record of the hardening and cooling of the concrete will be obtained."

MOOGERAH



... an aboriginal word,
meaning 'home of the
Thunder Storms'.

It is the name of the vast
new dam now being built
by the Queensland
Government Authority
to harness 20,000 million
gallons of water for the
irrigation of new
Australian pastures.

Lissapol N has been specified
for use in the construction.

This is the I.C.I. agent which has
proved invaluable in obtaining
workable concrete mixes of
maximum compaction.




LISSAPOL N

Full information on request

IMPERIAL CHEMICAL INDUSTRIES LIMITED LONDON SW1 ENGLAND

K192

Pattern of service in the concrete age



Working to schedule

Precast reinforced concrete frame three storeys high 132' 0" x 30' 0" erected by five men in three weeks.

Two components only—full-height columns and large area floor slabs, permitting varying plan form to suit particular schemes. Four of these structures erected for the United Kingdom Atomic Energy Authority Establishment, Winfrith Heath, Dorset.



Three Fold Service

Modular offer the combined services of consultation, design, manufacture and construction.

Modular will manufacture and erect to your designs.

Modular are specialists in precast structural concrete combined with integral finishes.



Modular
concrete

Whatever your concrete problem, the Modular Concrete Company's practical experience and technical resources are at your service.

SPECIALIST ENGINEERS & CONTRACTORS

THE MODULAR CONCRETE CO. LTD. (Construction Division)
1260 London Road, Norbury, S.W.16. Telephone: POLlards 5000

Bulletins Received.

"Structural Frameworks for Single-storey Factory Buildings." By H. V. Apar. Department of Scientific and Industrial Research. Factory Building Studies No. 7. (London: H.M.S.O. 1960. Price 4s.)

This paper describes how costs are affected by type of roof, span of roof, column spacing, clear height, and loading. A general discussion of the influence of structural type on the satisfaction of other functional requirements is given.

"Experiments on Concrete Bars: Expansions during Storage in Climate Room." By A. Eisen and O. Glarbo. (Copenhagen: The Danish National Institute of Building Research. 1960. In English. Price Kr. 12.)

This document is an interim report of research now proceeding under the auspices of the Committee on Alkali Reactions in Concrete.

"Beiträge zur Lösung von Scheibenproblemen." By R. Mathys. (Zürich: Verlag Leeman. In German. 1960. Price Swiss Fr. 12.)

"Platten mit freien Rändern." By H. von Gunten. (Zürich: Verlag Leemann. In German. 1960. Price Swiss Fr. 12.)

"Archiwum Inzynierii Ladowej." (Warsaw: Polska Akademia Nauk. Vol. VI. In Polish. 1960. Price 25 Złote.)

"Thermal Conditions in the Ground from the Viewpoint of Foundation Work, Heating and Plumbing Installations and Draining." By O. Vuorelainen. (Helsinki: State Institute for Technical Research, Finland. In English. 1960. No price stated.)

"Bulletin of the Polytechnic Institute of Jassy." (Jassy: In Roumanian, Russian, French and English. New Series Vol. V. 1959. No price stated.)

"The Problem of the Safety of Arch Dams." By M. Rocha and J. Laginha Serafim. Memorandum No. 142. National Laboratory of Civil Engineering of Portugal. (In Portuguese. 1960. No price stated.) Deals with studies of models.

"R.I.L.E.M. Bulletin." Nos. 8 and 9. (In French and English. 1960. No price stated.)

Bulletin No. 8 contains the papers on "Model Structures" presented at the Symposium in Madrid in 1959. Bulletin No. 9 contains the papers on the "Influence of Time upon Strength and Deformation of Concrete" presented at the Symposium in Munich in 1958.

A Large Prestressed Concrete Transmission-line Tower.

WHAT is thought to be the largest prestressed concrete transmission-line tower in the world has been erected near Pittsfield, Massachusetts, U.S.A. The structure is 99 ft. high and weighs 74 tons. The two legs of the tower are embedded for a length of 4 ft. 6 in. into sockets in twin reinforced concrete bases, each of




which is supported on four piles driven 80 ft. into the ground. The legs and the cross-arms, which are 93 ft. long, are hollow in order to reduce the weight. The legs and cross-arm are 18 in. by 36 in., the thickness of the wall being 5 in. The braces comprise four solid members 12-in. square, pin-jointed at the columns, and welded and grouted at the central meeting point. The tower is stabilised by wire guys.

The tower was supplied by the Prestressed Concrete Institute (of U.S.A.) as a contribution to a project for which the General Electric Co. (of U.S.A.) is responsible. The accompanying illustration is from "Concrete Products", February 1961.

Patent Applications for Prestressed Concrete.

Culverts and Pipes.


APPARATUS for prestressing constructions 10 of concrete by means of a tensioned cable 11 comprises movable shoes 15, having grooves 16 in which the cable 11 is located, which are adapted to slide on



fixed shoes 14 embedded in the concrete, lubricant being retained in recesses 18 in the bases of the shoes 15 by packing 20. The shoes are made of cast iron and the bearing surfaces are treated with sulphur. A plurality of recesses may be formed in the base of each shoe 15. The lubricant is preferably a mixture of bisulphide of molybdenum and thick grease with a small quantity of colloidal graphic. Conduits may be provided through which lubricant under pressure is supplied.—No. 840,982. Ateliers Partiot Cementation. April 26, 1957.

Runways and Roads.

In the prestressing of concrete slab structures such as airfield runways, roads or the like, each concrete slab is lifted, as by jacking means, so that it is supported clear of the ground and a prestress is applied to the slab after or during lifting of the slab. The jacking means may be applied to lift and support each slab by forming a plurality of holes in spaced positions in each slab through which jacking thrust bars can project down to the surface of the ground beneath the slab or



preferably on to a bearing plate on the ground. The jacking means may comprise a block 25, Fig. 3, secured on the underside of the slab 2 when cast, and having a threaded bore 26 adapted to receive a screw threaded lower end 29 of a rotatable thrust bar 28. The block 25 is located at the lower end of a steel lining tube 27. Alternatively hydraulic or pneumatic jacking means 16 may be applied between the upper end of the thrust bar 9, Fig. 1, and a stirrup 10 which is wedged into a steel tube 3 lining the hole 1 in the slab 2. After the jacking operation is completed the stirrup 10 and the bar 9 may be locked together by means of a clamp 17 and opposed serrated surfaces 18, so as to enable the jacking means 16 to be removed whilst maintaining the support of the slab at this point. In an



20-STOREY FLATS AVONDALE SQ S.E.1

Clients: The Corporation of London

Architects: Sir Lancelot Keay, Basil G. Duckett & Partners

Consulting Engineers: Ove Arup & Partners

Main Contractors: Pauling & Co. Ltd.

PAULING

RUSH & TOMPKINS - PAULING GROUP

GREAT BRITAIN, SOUTH AFRICAN REPUBLIC, CANADA, BRITISH GUIANA, ADEN

FOUR OUT OF FIVE LARGE

Strand


contracts in the U.K. use CCL anchorages

 $1\frac{1}{8}"$ *Spiral*
anchorages

CCL Spiral Anchorages are used extensively, both at home and overseas, due to their advanced design and reliability under site conditions. These all-metal, embedded type anchorages provide additional safety against bad concrete compaction.

**For helpful advice or
technical information write to:**

CABLE COVERS LIMITED • St Stephen's House • (Technical Service Dept) • Westminster S.W.1



alternative embodiment, each slab is lifted by water injected under pressure underneath the slab through non-return valves 36, Fig. 4, and tubes 35a lining holes 35 in the slab. In order to prevent escape of water from beneath the slab a thin waterproof membrane 38, e.g. of polyethylene sheet, is provided. A layer of coarse sand 39 is laid over the membrane 38 and is covered by a layer of building paper 40. The membrane 38 is turned back inwardly at its margins 41 to overlie the margins of the building paper 40. A number of drainpipes 42 are provided for draining water from below the slab after the lifting operation.—No. 853,418. D. H. Lee. March 24, 1959.

Courses at the Road Research Laboratory.

COURSES will be held at the Road Research Laboratory during the autumn of 1961 and, as in previous years, they will deal with the fundamental properties of road materials and with the results of research and their application in modern practice. The subjects and date of some of the courses are as follows.

Concrete.—26 September to 5 October and 10 to 19 October.

Soil Mechanics.—21 to 28 November, and 5 to 12 December.

The fee for each course is £12 12s. Applications must be received by the 29 June, 1961. Forms of application can be obtained from the Director, Road Research Laboratory, Harmondsworth, West Drayton, Middlesex.

FREE LECTURE

A lecture on "THE ULTIMATE SHEAR STRENGTH OF REINFORCED CONCRETE BEAMS" will be given by CHARLES ERDEI, B.Sc. Eng. (Hungary), on 10th July 1961, at 6.30 p.m., at the Friends House, Euston Road, London, N.W.1. (Garden entrance—Rooms 8-9.)

Admission will be by ticket only, and early reservations are advised—they are free and obtainable by post only from NEWTONIAN LTD., 473 Hornsey Road, London, N.19.

UNIVERSITY OF MELBOURNE

SENIOR LECTURER IN CIVIL ENGINEERING

Applications are invited for the above-mentioned position. Applicants should have had experience in Concrete Technology and Structural Design.

The salary range is £A2,480 to £A2,950 per annum. Initial salary will be determined according to qualifications and experience. Superannuation similar to P.S.S.U. in Great Britain will be provided.

Conditions of appointment may be obtained from THE SECRETARY, ASSOCIATION OF UNIVERSITIES OF THE BRITISH COMMONWEALTH, 36 Gordon Square, London, W.C.1.

Applications close, in Australia and London, on 25th July, 1961.

MISCELLANEOUS ADVERTISEMENTS.

Situations Wanted, 5d. a word: minimum, 12s. Situations Vacant, 6d. a word: minimum, 15s. Other miscellaneous advertisements, 6d. a word: minimum, 15s. Displayed advertisements, 40s. per column inch. Box number 1s. extra.

Advertisements must reach this office, 14 Dartmouth Street, London, S.W.1, by the 26th of the month preceding publication.

SITUATIONS VACANT.

SITUATIONS VACANT. Reinforced concrete and structural steelwork designers and detailers required at Bristol head office and in the London office. Permanent positions covering most fields of reinforced concrete and steelwork design. Pension and insurance schemes. Attractive salaries. Full details to NORMAN CONSULTANTS LTD., Beacon House, Queen's Road, Clifton, Bristol, 8.

SITUATIONS VACANT. Consulting engineers have vacancies for the following: Reinforced concrete designers with A.M.I.Struct.E.; Designer-detailers with H.N.C. or similar; Detailers with minimum two years' experience. The positions are permanent, with opportunity for advancement. Modern office and pleasant conditions. Salaries in accordance with experience. Apply BYLANDER, WADDELL & PARTNERS, 169 Wembley Park Drive, Wembley, or 10 Calver Street, Sheffield.

SITUATIONS VACANT. A few experienced reinforced concrete designer-detailers required for interesting and progressive posts with consulting engineers at their offices in Cannon Street, London, E.C.4. Salary range (£50-£1500). Luncheon vouchers. Pension scheme. Apply EDWARD A. PITCHER & PARTNERS, 55-60 Cannon Street, London, E.C.4. Telephone: City 2292.

LYTAG LIMITED

A Laing Company engaged in the production of lightweight aggregate requires

TECHNICAL DEVELOPMENT OFFICER

Applicants should be 30-45 years of age, and should possess A.M.I.C.E. or A.M.I.Struct.E., having some years' experience in reinforced concrete design. The successful applicant will be responsible for developing the uses of Lytag in all its phases, and be required to discuss results and methods with the appropriate authorities. It is envisaged that the position will be progressive, and eventually form an important part of the sales organisation of the company.

PRODUCTION DEVELOPMENT OFFICER

Applicants should be between 30-45 years of age and qualified mechanical engineers with experience of the operation of full-size factories. A background of the sintering industry would be an advantage. The position offers excellent prospects of advancement, and it is expected that the position could develop into that of Production Manager in charge of several factories.

Pension scheme and other progressive benefits.

Apply, giving brief details in the first instance, to THE GROUP PERSONNEL MANAGER—(LY.5)—JOHN LAING AND SON LTD., LONDON, N.W.7.

Would you like to help

**YORKSHIRE'S VAST
AND IMMEDIATE
MOTORWAY
PROGRAMME ?**

The Doncaster By-pass Motorway will be opened by August Bank Holiday. Wouldn't you have liked to have taken a part in this £6 million scheme?

Now is a unique opportunity for you to get design and construction experience on the Sheffield-Leeds Motorway in the West Riding. The project offers difficult, but interesting and satisfying jobs with good promotion prospects for a large number of road and bridge engineers of all grades up to lettered scale "E".

Besides the 35 miles Sheffield-Leeds Motorway the County Council is starting the location of the 33 miles East-West Motorway as well as numerous other dual carriageway schemes.

Write at once to

**THE COUNTY ENGINEER AND SURVEYOR
COUNTY HALL, WAKEFIELD, YORKS**

**for a brochure giving details of these PERMANENT
STAFF appointments**

SITUATIONS VACANT. Harrow reinforced concrete engineers and contractors require experienced detailing-draughtsmen. Five-days' week; interesting work; modern offices; pension scheme after qualifying period. Write **BURRUMS**, 167-173 Imperial Drive, Harrow, or telephone for appointment Field Ead 7701.

SITUATION VACANT. Representative. Opportunity for enthusiastic young man to obtain position on sales technical staff of company with renowned product indispensable to reinforced concrete construction. Initially mobile over 50-miles radius of South Coast—London. Knowledge of reinforced concrete, and holding a driving licence advantageous. Applicants must be of pleasant personality, keen, energetic, conscientious, adaptable, and should have been educated to the standard of G.C.E. Written applications, treated in strict confidence, with full particulars, details of qualifications, etc., to Box 4754, **CONCRETE AND CONSTRUCTIONAL ENGINEERING**, 14 Dartmouth Street, London, S.W.1.

RICHARD HILL LIMITED

REINFORCED CONCRETE ENGINEERS

Designers and detailers are required for a wide variety of reinforced concrete structures in our offices in London, Middlesbrough, Manchester and Birmingham. Several vacancies in London and Middlesbrough for designers experienced in project work. Write, or telephone, one of the following for interview:

J. E. GUEST, P.O. Box 29, Middlesbrough. (Middlesbrough 46092).

W. E. A. SKINNER, 7 Cleveland Row, London, S.W.1. (Whitehall 3100).

D. H. HALSTEAD, 19B School Road, Sale, Cheshire. (Sale 8277).

ENGINEERING DESIGNER/DRAUGHTSMEN

required by

AIR MINISTRY · LONDON

Salary (inner London scale) Grade II, £1,048-£1,315; Grade III, £658-£1,048 (£866 at age 25). Starting salary depends on age, qualifications and experience.

Structural engineering designer/draughtsmen for reinforced concrete work of all types (Grades II and III).

Candidates should have served a recognised apprenticeship or have had equivalent training and also adequate practical experience. Possession of recognised technical qualification an advantage—financial assistance and time off may be allowed for recognised courses of study for technical qualifications. Five-days' week with 18 days' paid leave per annum initially. Promotion and pension prospects. Some overseas tours with special allowances in addition to salary.

Applicants, who must be natural born British subjects, should write, quoting Kings Cross O/N 806, to **AIR MINISTRY, W.G.2, LACOR HOUSE, THOROLD ROAD, LONDON, W.C.1**, or to any **EMPLOYMENT EXCHANGE**, giving age, details of training, qualifications and full particulars of former posts held. Candidates selected will normally be interviewed in London and certain expenses reimbursed. Only candidates selected for interview will be notified.

SITUATIONS VACANT. Reinforced concrete engineers require engineers, designers and detailers/draughtsmen. Interesting work, five-days' week, luncheon vouchers, own pension scheme, etc. Salaries in accordance with experience. Write or telephone to **THE REINFORCED CONCRETE STEEL CO. LTD.**, 34 Victoria Street, London, S.W.1. Telephone: Tate Gallery 4792.

SITUATIONS VACANT. Reinforced concrete designer-detailers and detailers required by **LEONARD & GRANT** in their South London and Edinburgh offices. Applicants should have three years' minimum experience in position applied for. Good salaries and prospects, luncheon vouchers, etc. Interview by appointment. Telephone: London, MACanlay 6477; Edinburgh, CAL 3807.

SITUATIONS VACANT. Reinforced concrete detailers required by consulting engineer near Hyde Park Corner. Small and friendly office with scope for gaining design experience in wide field. Five-days' week. Holiday arrangements honoured. Apply, stating experience and salary required, to **S. JAMPEL**, 33 Knightsbridge, London, S.W.1.

SITUATION VACANT. Reinforced concrete designer-detailer required for small consultants' office near Finchley Road London Transport Station, Hampstead. Able to work without supervision. Telephone Maids Vale 0375 for appointment.

SITUATIONS VACANT. SPECIALIST REPRESENTATIVES—vacancies exist in London and Birmingham for two Specialist Representatives to promote the sale of a new type of concrete anchor being imported from the U.S.A. Knowledge of concrete construction is essential, together with the ability to carry out effective demonstrations. The positions offer great scope for advancement in an expanding company. Salary commensurate with experience and successful applicant will be admitted to the Group Pension Scheme. Car provided, or generous allowance if car owner. Applicants should send full details in writing to **MANAGING DIRECTOR, GREENHAM TOOL CO. LTD.**, 618 London Road, Isleworth, Middlesex.

Join the **BRC**

team of

EXPERIENCED

REINFORCED

CONCRETE

DESIGNER/DETAILERS

and DRAUGHTSMEN

at any of the Design Offices at

STAFFORD	LEEDS
LONDON	LIVERPOOL
BIRMINGHAM	MANCHESTER
BRISTOL	NEWCASTLE
CHELMSFORD	GLASGOW
DUBLIN	

* Apply

Chief Engineer:

A. P. Mason, B.Sc., M.I.C.E., M.I. Struct. E., M.A.S.C.E.
THE BRITISH REINFORCED CONCRETE
ENGINEERING CO. LTD., STAFFORD

SITUATION VACANT. Designer of shuttering and builders' plant required by manufacturer. Concrete mould experience advantageous. Full details of experience and qualifications to THE CHIEF ENGINEER, A.B. MOULD & CONSTRUCTION CO. LTD., Vulcan Works, New Addington, Croydon.

STRUCTURAL CONCRETE

THE SCOTTISH CONSTRUCTION COMPANY LTD.

require immediately
Design Office Staff of all grades for an expanding programme of precast and in-situ concrete structures and for development work. Salaries range up to £900 for draughtsmen and detailers, and up to £1,600 for qualified senior top-class engineers. Good prospects and conditions.

Applications, in strict confidence, to THE CHIEF CIVIL ENGINEER, THE SCOTTISH CONSTRUCTION CO. LTD., Sighthill Industrial Estate, Edinburgh.

SITUATIONS VACANT. Reinforced Concrete Designers, Detailers and Draughtsmen required at Glasgow, Newhouse, Edinburgh, Gateshead, Manchester and Altrincham. Progressive positions with established company. Five-days' week. Non-contributory pension scheme and profit-sharing bonus. Apply to the Divisional Engineer at any of the Branch Offices or to the Regional Engineer, THE SQUARE GRIP REINFORCEMENT CO., LTD., Market Street, Altrincham, Cheshire.

PRECAST CONCRETE

Structural Engineer experienced in prestressed and precast design required to take charge of the Structural Drawing Office of a rapidly expanding contracts department. Position has excellent prospects and offers a wide scope of design to an Engineer interested in the development of precast structures. Pension scheme in operation. Write, giving details of experience—in confidence—to THE CONTRACTS MANAGER, TARMAC VINCLUM LTD., Ettingshall, Wolverhampton.

Experienced Reinforced Concrete **DESIGNERS & DETAILERS**

with minimum H.N.C. are required by a leading firm of Consulting Engineers for their LONDON and EPSOM, SURREY, offices. These are permanent positions with a five-days' week, luncheon vouchers and pension scheme. Please write fully to the Personnel Manager.

W. S. ATKINS & PARTNERS
158 Victoria Street London, S.W.1

LAING

JOHN LAING AND SON LIMITED

require

ENGINEERS

for general site engineering services on contracts throughout the country. Applications are invited from qualified and part qualified men and from men with good instrument experience. This is an opportunity to join a well-integrated team with permanent and pensionable employment with the Company.

Apply, giving brief details of past experience, to:

THE GROUP PERSONNEL MANAGER (S.E.11),

JOHN LAING & SON LTD.,

London, N.W.7.



EXECUTIVE APPOINTMENTS LIMITED
78 Wigmore Street, London, W.1

An old-established and substantial British trading company in Nigeria seeks

TECHNICAL REPRESENTATIVE **Construction Equipment**

Candidates 30-45, of at least grammar school educational standard, must have sound civil engineering experience and be familiar with modern uses of steel scaffolding, shuttering, etc., and must be capable of designing and preparing drawings for new project.

SALESMEN **Building Materials**

Candidates 28-35 of good education must have had practical experience in the building industry and a successful record in selling to that industry.

All appointments offer a career in a virile and expanding organisation, starting salaries in the range £1,500-£2,000, pension, free furnished quarters, car and generous passage, paid leave. (WH. 108)

Please write briefly in strictest confidence to the Managing Director, quoting the reference number and indicating the position required. No identities divulged without permission.

Truscon

Applications are invited from reinforced concrete designers, detailers, and draughtsmen for vacancies which exist at a number of our structural design offices. We are looking for men with first-class experience who will help to maintain our own tradition of quality, combined with speed and economy. In London, in particular, designer applicants should have had good experience of, and an aptitude for, project work. Address your letter personally to one of the following:

LONDON	V. Weber, B.Sc., A.C.G.I., M.I.C.E., M.I.Struct.E., Truscon House, 35/41 Lower Marsh, S.E.1.
HARLOW	P. B. Wood, B.Sc.(Tech.), A.M.I.Struct.E., 13 Market House, Stone Cross, Harlow.
BIRMINGHAM	B. W. Cooper, B.Sc., D.I.C., A.M.I.C.E., George House, George Road, Edgbaston, Birmingham 15.
MANCHESTER	H. Heller, B.Sc., A.C.G.I., A.M.I.C.E., 50 Seymour Grove, Manchester 16.
GLASGOW	W. H. Sneddon, M.I.Struct.E., 10 India Street, Glasgow C.2.

- expanding company
- good reputation
- progressive approach
- good salaries
- profit-sharing scheme
- pension scheme
- good holidays
- free sick pay scheme
- five day week
- overtime paid
- opportunities for advancement
- security

SITUATIONS VACANT. Detailers experienced in reinforced concrete required for London professional office. The work is varied, comprising all types of construction in concrete and steel, and offers scope for anyone interested in gaining design experience. Permanent position with excellent prospects. Five-days' week. Apply, stating full experience, to **FARMER & DARE**, Romsey House, Tufton Street, London, S.W.1.

SITUATIONS VACANT. **CLARKE, NICHOLLS & MARCEL** require experienced reinforced concrete designer-detailers and draughtsmen for their Bristol and Cardiff offices. Positions are pensionable, and offer first-class experience for those studying for professional qualifications. A senior structural engineer is also required for the Cardiff office, and preference would be given to an A.M.I.Struct.E. Apply to 10 Apsey Road, Bristol 8, or South Wales Institute of Engineers Building, Park Place, Cardiff.

SITUATIONS VACANT. Consulting engineer, **W. PASZKOWSKI, D.I., A.M.I.C.E.**, has vacancies for assistant engineers and reinforced concrete detailers. Variety of civil and structural work. Apply, 1 Gregory Place, Kensington, London, W.8.

SITUATION VACANT. Gillingstone require a qualified reinforced concrete engineer for in situ and precast construction. The appointment has excellent opportunities and pension scheme, and headquarters could be at Leeds or Feltham, Middx. Apply by letter only, with details of experience, salary, age, etc., to **GILLINGSTONE**, Feltham, Middx.

ENGINEER

required

to prepare project designs in precast, prestressed and reinforced concrete. Salary up to £1,500 will be paid to qualified applicant with wide experience. Apply in writing to **THE CHIEF ENGINEER, LONDON FERRO-CONCRETE CO., LTD.**, Maxted Close, Hemel Hempstead, Herts.

E. J. COOK & CO. (ENGINEERS) LTD.

Invite applications from reinforced concrete designers who are at present earning £1100-£1400 per annum and are prepared to accept responsibility. Write or telephone for application form from 34 South Side, Clapham Common, London, S.W.4. (MACaulay 5592.)

GKN

TECHNICAL REPRESENTATIVES CONCRETE REINFORCEMENT

A Group Company which is principally concerned with the manufacture and marketing of all types of steel reinforcement for concrete wishes to appoint a technical representative based on London to assist in covering the professional engineering field.

Experience in reinforced concrete and an appropriate technical qualification, together with some commercial aptitude, will be required. The preferred age group is 25/32 and the commencing salary will be in accordance with qualifications and experience.

Applications, giving details of age, experience and qualifications, should be addressed to the **GROUP PERSONNEL OFFICE, GKN House, 22 Kingsway, London, W.C.2**, quoting reference CE/1.



TAYLOR WOODROW CONSTRUCTION LIMITED

require

DESIGNERS: with experience in design and efficient detailing of large reinforced concrete and/or steel structures. There are opportunities for senior design appointments.

DETAILERS: capable of quick and accurate reinforcement detailing and some design under supervision.

DRAUGHTSMEN: must be neat and accurate workers with experience of reinforced concrete or structural steel outline and detail work.

These vacancies occur at the Head Offices in Southall. Applicants should either telephone **WAX 2366** (**Mr. E. A. Woolnough—Atomic Power Design**) (**Mr. R. H. Walpole—General Industrial Design**) or write to the

**Personnel Manager,
345, Ruislip Road,
Southall, Middlesex.**

Alternatively, senior personnel will be available for informal discussions about these posts at our offices at 10 Park Street, London, W.1, from 5.30 p.m. on the Thursday following this advertisement.

DESIGNER DRAUGHTSMAN

required by

WESTMINSTER CONSULTING ENGINEER

Applicants should be of H.N.C. or graduate standard with 7 to 10 years' experience and capable of supervising small drawing office engaged on reinforced concrete and structural steelwork. Salary £900 to £1,200 according to experience. Write, giving age, qualifications and experience, to Box 4763, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

STRUCTURAL ENGINEERING

Edinburgh architects, expanding their engineering side, urgently require structural engineer and draughtsman. Experience in reinforced concrete is required but applicants should be capable of dealing with all building materials including brick and timber.

These are jobs of special interest to anyone wishing to work in close collaboration with all members of the professional design team and wishing to study the whole building process from initiation to handing over.

Personal and congenial working conditions.

Apply **BOX 4765, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.**

BRITISH RAILWAYS RESEARCH DEPARTMENT

The following vacancies exist in a modern chemical laboratory adjacent to Alexandra Palace, London. Scientific Officer, Grade 2. Building Materials Laboratory.

Academic/professional qualifications essential. Thorough knowledge of the chemistry of building materials. Salary range £780-£1,145 per annum. (Commencing salary according to qualifications and/or experience.)

Senior Technical Assistant, Building Materials Laboratory.

Applicants must have at least a Higher National Certificate in chemistry and a good chemical and practical knowledge of building materials and their uses. Salary range £945-£1,145 per annum.

Superannuation and travel facilities. Medical examination. Applications within 14 days, stating age, qualifications and experience, to

THE DIRECTOR OF RESEARCH
BRITISH RAILWAYS
RESEARCH DEPARTMENT
222 MARLBOROUGH ROAD
LONDON, N.W.1

CIVIL/STRUCTURAL ENGINEER

Applications are invited from Corporate Members of the Institutions of Civil/Structural Engineers for a permanent appointment in the Civil Engineering Section of the National Coal Board, West Midlands Division, Himley Hall, Nr. Dudley, Worcs.

The appointment will be within the salary range of £1,000-£1,550 per annum, and the starting salary will be commensurate with qualifications and experience.

The Division has on hand a large programme of interesting work offering experience of a varied nature.

The appointment is superannuable.

Applications quoting CCE on forms obtainable from DIVISIONAL CHIEF STAFF OFFICER, NATIONAL COAL BOARD, Himley Hall, Nr. Dudley, Worcs., to be returned by 26th June 1961.

CHEMICAL BUILDING PRODUCTS LIMITED

Manufacturers of

CONCRETE ADDITIVES

which include

WATERPROOFERS,
PLASTICISERS
HARDENERS
AND ACCELERATORS

require a

TECHNICAL ASSISTANT

(up to 35)

in the

SALES OFFICE

to attend to technical enquiries concerning the application of products and undertake occasional advisory visits to sites.

We are looking for a man who has experience in actual construction, or has been technically connected with this field.

A good starting salary will be paid. Applicants may qualify for housing. Please write in confidence to the company, **Cleveland Road, Hemel Hempstead, Herts.**

SITUATION VACANT. Reinforced concrete engineer required, experienced in designing structural precast concrete framework, to supervise drawing office in Essex (approx. 20 miles from London). Good salary paid for this permanent position in modern drawing office. Pension scheme in operation. Box 4762, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

SITUATIONS VACANT. Reinforced concrete designers and detailers—YOUR OWN BUREAU—no fees. Permanent positions. Call **BUSINESS VACANCIES BUREAU LTD.** 32 Victoria Street, London, S.W.1. Telephone Abbey 7200.

Truscon's Harlow Office

—is delightfully situated in this thriving new town where houses for renting are still available. We have at present vacancies for an experienced reinforced concrete designer, and for detailers and draughtsmen. If applicants for these posts would care to visit Harlow, with their wives, we should be happy to pay their travelling expenses. Please write in the first instance to **P. B. WOOD, TRUSCON LIMITED, 13 Market House, Stone Cross, Harlow, Essex.**

SITUATION WANTED.

SITUATION WANTED. Reinforced concrete designer-drafter, 27, seeks job, not necessarily London area, where design office and site experience are available side by side. Willing to enter into a contract on reasonable conditions. Box 4761, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

BUSINESS OPPORTUNITY.

BUSINESS OPPORTUNITY. Consulting structural engineer with office space and drafting capacity available in Victoria Street in excess of present requirements and having continuity of work from small number of clients would welcome suggestions for association with established or aspiring consultants or others. Please reply, in confidence, to Box 4764, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1

FOR SALE.


HIGH-QUALITY FORKLIFT TRUCKS!!!
PETROL, DIESEL AND ELECTRIC
MODELS

By Coventry Climax, Conveyancer, Wingrove & Rogers, Lansing Bagnall, etc. From £450-£1000.
Full details on application. **SPEED ELECTRICS**, Dept. CCE., Church Street, Basford, Nottingham. Tel. 75716.

FOR SALE. Refuse containers, repaired and modified. General metalwork, all types. **E. STEPHENS & SONS LTD.**, Bath Street, London, E.C.1. Clerkenwell 1731.

PATENTS.

PATENT. The proprietor of British Patent No. 771,397, which relates to a Concrete Block Forming Machine, is desirous of exploiting the invention by way of licence or sale. Enquiries should be addressed to **ANDREWS & BYRNES**, 201 Bank Chambers, 329 High Holborn, London, W.C.1.



Trent Gravels
10,000 tons per week

Washed & Crushed $1\frac{1}{2}$ in. to $\frac{1}{2}$ in.

We are the leading suppliers of high-class concrete aggregates in the area shown above. Prompt deliveries guaranteed and keen competitive prices quoted. Send for samples and prices.

TRENT GRAVELS LTD

ATTENBOROUGH

Telephone: Nottingham 25 4255

NOTTS

A NEW "CONCRETE SERIES" BOOK**FOUNDATION FAILURES**

By C. SZECHY, D.Sc.

The Author, who is Professor of Foundation Engineering at Budapest, investigated numerous cases of the failure of foundations in Hungary, and the book includes the results of these examinations together with reports of many other failures in various parts of the world.

The causes of failures are diverse, but the principal possible causes in design or construction are classified as follows:

Insufficient or wrongly interpreted site investigation.

Unsuitable structures and foundations.

Defective execution.

External influences.

115 pages.

123 diagrams and photographs.

Price 20s.; by post 21s. 5 dollars in Canada and U.S.A.

CONCRETE PUBLICATIONS LTD.

14 DARTMOUTH STREET, LONDON, S.W.1

OVER 2,000 TONS OF TENTOR BARS WENT INTO THE BUILDING OF THE NEW BBC TELEVISION CENTRE AT WHITE CITY

Tentor Bars for concrete reinforcement have a high tensile and bond strength; save up to 15% of the cost of plain rounds; require no hooks; can be supplied cut or bent to specifications, in sizes from $\frac{1}{2}$ " to 1 $\frac{1}{4}$ ".

Tentor Bars are supplied by the following companies and their branch offices:—

R.R.C. STEEL LTD, Silkmore Lane,
Stafford. Stafford 444

G.K.N. REINFORCEMENTS LTD, 22 Kingsway,
London, W.C2. CHAncery 1616

MCCALL & CO. (SHEFFIELD) LTD, P.O. Box 41,
Sheffield. Rotherham 2076

STEEL, FRISH & TOZER, LTD, Branch of The United Steel
Companies Ltd, The Ickles, Sheffield. Sheffield 41011



The
TENTOR BAR
Company Limited

Architects: Norman & Dawbarn. Civil Engineer to the BBC: M. T. Tudorbery C.E.E. Main Contractors: Superstructure: Higgs & Hill Ltd. Foundations: G. Wimpsey & Co. Ltd.

THE TENTOR BAR COMPANY LTD.



GEN HOONE • 22 KINGSWAY • LONDON W.C2 • TEL: CHANCERY 1616 • GRAMS: TENTOR • WESTCENT LONDON

SITUATION WANTED.

SITUATION WANTED. Reinforced concrete designer-draftman, 27, seeks job, not necessarily London area, where design office and site experience are available side by side. Willing to enter into a contract on reasonable conditions. Box 4764, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

BUSINESS OPPORTUNITY.

BUSINESS OPPORTUNITY. Consulting structural engineer with office space and drafting capacity available in Victoria Street in excess of present requirements and having continuity of work from small number of clients would welcome suggestions for association with established or aspiring consultants or others. Please reply, in confidence, to Box 4764, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1

FOR SALE.

HIGH-QUALITY FORKLIFT TRUCKS!!!
PETROL, DIESEL AND ELECTRIC
MODELS


By Coventry Climax, Conveyancer, Wingrove & Rogers, Lansing Bagnall, etc. From £450-£1000.

Full details on application. SPEND ELECTRICAL Dept. CCE., Church Street, Basford, Nottingham
Tel. 75716.

FOR SALE. Refuse containers, repaired and modified. General metalwork, all types. E. STEPHENS & SON LTD., Bath Street, London, E.C.1. Clerkenwell 1734.

PATENTS.

PATENT. The proprietor of British Patent No. 771,397, which relates to a Concrete Block Forming Machine, is desirous of exploiting the invention by way of licence or sale. Enquiries should be addressed to ANDREWS & BYRNE, 201 Bank Chambers, 329 High Holborn, London, W.C.1.



Trent Gravels
10,000 tons per week

Washed & Crushed $1\frac{1}{2}$ in. to $\frac{1}{2}$ in.

We are the leading suppliers of high-class concrete aggregates in the area shown above. Prompt deliveries guaranteed and keen competitive prices quoted. Send for samples and prices.

TRENT GRAVELS LTD

ATTENBOROUGH

NOTTS

Telephone: Nottingham 25 4255

A NEW "CONCRETE SERIES" BOOK**FOUNDATION FAILURES**

By C. SZECHY, D.Sc.

The Author, who is Professor of Foundation Engineering at Budapest, investigated numerous cases of the failure of foundations in Hungary, and the book includes the results of these examinations together with reports of many other failures in various parts of the world.

The causes of failures are diverse, but the principal possible causes in design or construction are classified as follows:

Insufficient or wrongly interpreted site investigation.

Unsuitable structures and foundations.

Defective execution.

External influences.

115 pages.

123 diagrams and photographs.

Price 20s.; by post 21s. 5 dollars in Canada and U.S.A.

CONCRETE PUBLICATIONS LTD.

14 DARTMOUTH STREET, LONDON, S.W.1

OVER 2,000 TONS OF TENTOR BARS WENT INTO THE BUILDING OF THE NEW BBC TELEVISION CENTRE AT WHITE CITY



Tentor Bars for concrete reinforcement have a high tensile and bond strength; save up to 15% of the cost of plain rounds; require no hooks; can be supplied cut or bent to specifications, in sizes from $\frac{1}{4}$ " to $1\frac{1}{2}$ ".

Tentor Bars are supplied by the following companies and their branch offices:—

B.R.C. STEEL LTD, Silkmore Lane,
Stafford. Stafford 444

G.K.N. REINFORCEMENTS LTD, 23 Kingsway,
London, WC2. CHAncery 1616

MCCALL & CO. (SHEFFIELD) LTD, P.O. Box 41,
Sheffield. Rotherham 2076

STEEL, FRICH & TOZER, LTD, Branch of The United Steel
Companies Ltd, The Ickles, Sheffield. Sheffield 41011



TENTOR BAR
Company Limited

*Architects: Moorman & Dawbarn Civil Engineer to the BBC:
M. T. Tudsbury C.E.S. Main Contractors: Superstructures
Higgs & Hill Ltd. Foundations: G. Wimpey & Co. Ltd.*

THE TENTOR BAR COMPANY LTD.



OPEN HOUSE • 23 KINGSWAY • LONDON WC2 • TEL: CHANCERY 1616 • GRAMS: TENTORED • WHITCENT LONDON



REINFORCED CONCRETE IS CONSTRUCTION AT ITS BEST

BRC FABRIC IS REINFORCEMENT AT ITS BEST

*Specialists in Reinforced Concrete Design
and Suppliers of Reinforcement*

THE BRITISH REINFORCED CONCRETE ENGINEERING CO. LTD., STAFFORD

London, Birmingham, Bristol, Chelmsford, Leeds, Leicester, Liverpool, Manchester, Newcastle, Cardiff,
Glasgow, Dublin, Belfast, Bulawayo, Calcutta, Johannesburg, Singapore, Vancouver

Export Sales: 54 Grosvenor Street, London W.1

BA-W. 1215

Published by CONCRETE PUBLICATIONS LTD., 14 Dartmouth Street, London, S.W.1. Telephone: Whitehall 4581
Printed by BUTLER & TANNER LTD., The Selwood Printing Works, Frome and London

